



# Tennessee Housing Development Agency

**Low-Income Housing Tax Credit Program**

**2026 Qualified Allocation Plan**

**Administered by: Multifamily Programs Division**

**Tennessee Housing Development Agency**

**Ralph M. Perrey, Executive Director**

**Approved by THDA Board of Directors: September 23, 2025**

**Approved by Governor Bill Lee: December 17, 2025**

**If you are a person with a disability and need an accessible version  
of this document, please contact THDA's 504 Coordinator at**

**[RRequest@thda.org](mailto:RRequest@thda.org)**

## Table of Contents

### PART I: ALL ALLOCATIONS

Section	Topic	Page
1	Introduction and Disclaimers	4
2	Definitions	9
3	THOMAS and Initial Application Submission Requirements	25
4	Program Fees	27
5	Development Team Members and Eligibility Thresholds	30
6	Mandatory and Threshold Requirements	36
7	New Construction and Rehabilitation Minimum Requirements	42
8	Construction Review Process	43
9	Final or Placed in Service Process	46
10	Compliance Requirements and Monitoring Process	50

### PART II: COMPETITIVE ALLOCATIONS ONLY

11	Limits on Housing Credit Allocations	64
12	Non-Profit Set-Aside	69
13	Economic Development Area Set-Aside	71
14	Permanent Supportive Housing for Homeless Set-Aside	73
15	New Construction General Priority Category	74
16	PHA General Priority Category	75
17	Initial Application Scoring	
	New Construction Only	77
	Rehabilitation of Existing Multifamily Housing	90
18	Competitive Housing Tax Credit Calendar of Events	102
19	Initial Application Eligibility and Scoring Review	103
20	Carryover Allocation Process	110
21	Housing Credit Exchange	114

### PART III: NONCOMPETITIVE ALLOCATIONS ONLY

22	Developments Financed with Tax-Exempt Bonds	115
----	---	-----

**PART IV: ADOPTION AND APPROVAL BY GOVERNOR**

23 Adoption and Approval by Governor

120

## PART I: ALL ALLOCATIONS

### Section 1: Introduction and Disclaimers

The Tennessee Housing Development Agency (“THDA”) administers the Low–Income Housing Tax Credit program in Tennessee. The Low–Income Housing Tax Credit (“Housing Credit”) program was created by the Tax Reform Act of 1986 under Section 42 of the Internal Revenue Code of 1986, as amended (“Section 42”), to encourage the construction and rehabilitation of rental housing for low–income individuals and families. Under Section 42(m), THDA is required to develop a Qualified Allocation Plan (“QAP”) to define the process by which it will allocate an annual amount of Housing Credit in Tennessee.

This QAP contains uniform resource locators to resources utilized by THDA in the application process, such as the Tennessee Growth Policy Act, Multifamily Tax Subsidy Project Income Limits, Qualified Census Tracts, designations of Difficult to Develop Areas, Fair Housing Act requirements, etc. “**Attachments**” are forms or documents, which must be submitted in the Tennessee Housing Online Management Administration System (“THOMAS”) as part of the Initial Application.

All QAP requirements, Initial Application requirements, and Code requirements must be met. These requirements include, without limitation, all applicable requirements of the THOMAS User Manual and use of all applicable forms and templates from the THOMAS Documents Page.

This QAP has been approved by the THDA Board of Directors and adopted by the Governor of Tennessee.

When this QAP calls for some THDA action, including but not limited to a determination, adjustment, review, evaluation, or exercise of discretion, all such actions will be at THDA’s sole discretion, whether specifically so stated or not.

No person or entity who submits an Initial Application has any right to an allocation of Housing Credit under this QAP based solely on the score assigned to their Initial Application. THDA decisions are final.

### **The QAP as Public Policy**

The policy surrounding this QAP is to use the Housing Credit allocated to Tennessee to create, maintain, and preserve affordable rental housing for low-income households. Specific objectives of this QAP are to:

- A. Make rental units affordable, in the areas of greatest need, to households with as low an income as possible and for the longest time period possible;
- B. Encourage development of appropriate housing units for persons with special needs, including individuals who are older persons, homeless, or have a disability;
- C. Allocate only the minimum amount of Housing Credit necessary to make a development financially feasible and viable throughout the credit period;
- D. Encourage Qualified Nonprofit Organizations to develop rental housing for low-income households;
- E. Encourage fair distribution of Housing Credit among counties and developers; and
- F. Allocate Housing Credit fairly.

### **Amendments**

THDA may amend any part of this QAP following public notice and approval by the THDA Board of Directors. Such amendment is expressly permitted by this QAP, and

the making of such amendment will not require further public hearings or approval by the Governor. THDA, in accordance with Section 42, may impose additional requirements in order to fulfill the objectives of its housing initiatives.

### **Site Changes**

A request for a Site change will only be considered if the original allocation of Housing Credit is returned and a new allocation of Housing Credit is made pursuant to Section 42(m)(1)(A)(iv) of the Code.

### **Document Review**

THDA will review and evaluate only those materials submitted in compliance with the requirements of this QAP. THDA is not responsible for missing, inaccurate, or incomplete documentation. THDA will not evaluate any materials submitted outside the deadlines for submission of such materials and will assume no obligation to request additional information from Applicants for any purpose.

THDA may require additional information and/or documentation if THDA determines that additional information is necessary for clarification and/or explanation. THDA's review of documents submitted with any Initial Application, including Initial Applications or documents submitted in connection with Housing Credit reserved or allocated under this QAP, is for THDA's own purposes and is not for the purpose of advising, certifying, representing, or warranting to others as to the feasibility or viability of any proposed development.

### **Adverse Action by Local Jurisdiction**

If, following the allocation of Housing Credit to a proposed development, the local jurisdiction in which the proposed development is located takes action that THDA, in its sole discretion, determines to be for the primary purpose of preventing the proposed development from satisfying applicable program requirements, THDA may lower the amount of Housing Credit available to that jurisdiction in future Qualified

Allocation Plans. Examples include, without limitation, “downzoning”, action regarding utilities or utility connections, action regarding required public roads, or action to prevent issuance of Certificates of Occupancy.

### **No THDA Liability**

No member, officer, agent, or employee of THDA shall have any personal liability with respect to any matters arising out of, or in relation to, this QAP, Housing Credit reserved or allocated under this QAP, or the monitoring of Housing Credit Developments.

THDA makes no representations or warranties to applicants, developers, owners, or anyone else as to compliance with Section 42, Treasury regulations, or any other laws or regulations applying to Housing Credit or Housing Credit Developments, or as to the feasibility or viability of any proposed Housing Credit Development.

### **Enforcement**

In the event THDA seeks enforcement of any matter connected with any reservation, allocation, or monitoring of Housing Credit, or any other matter connected with Housing Credit, THDA shall be entitled to recover all damages, costs, expenses and fees, including without limitation, all court costs, all legal fees and expenses, and all staff time, from any party connected to or with any Housing Credit Development.

### **False Statements**

- A. Tennessee Code Annotated, Section 13–23–133, makes it a Class E felony for any person to knowingly make, utter, or publish a false statement of substance or aid or abet another person in making, uttering, or publishing a false statement of substance for the purpose of influencing THDA to allow participation in the Housing Credit Program. Any and all statements contained in any materials, including without limitation, an Initial Application

and any other applications, documents, letters, opinions, or certifications, submitted to THDA in connection with any Initial Application, subsequent applications or in connection with Housing Credit reserved, allocated or monitored for compliance under this QAP or otherwise made by an Applicant or other person connected in any way with Housing Credit reserved, allocated or monitored for compliance under this QAP are statements of substance made for the purpose of influencing THDA to allow participation in the Housing Credit Program.

- B. By submitting any materials, including without limitation, an Initial Application and any other applications, documents, letters, opinions, or certifications to THDA in an effort to obtain or maintain Housing Credit, the Applicant and all parties connected with the development proposed in the Initial Application acknowledge and agree (1) they are entering into a contract with THDA; and (2) they intend for THDA to rely on and seek enforcement of all selections or statements (written or oral) made with respect to any reservation, allocation or monitoring of Housing Credit by any and all means available, including, without limitation, specific performance; and (3) they are knowingly making, uttering or publishing or aiding and abetting others in making, uttering or publishing statements of substance for the purpose of influencing THDA to allow participation in the Housing Credit program.

## **Section 2: Definitions**

20/50 Test – The 20/50 Test is a federal minimum set-aside that may be elected by an Applicant for Housing Credit that requires at least 20% of the units in a Housing Credit Development to be both rent restricted and occupied by households whose income is less than or equal to 50% of area median gross income (“AMI”). This is an irrevocable election made in an Initial Application.

40/60 Test – The 40/60 Test is a federal minimum set-aside that may be elected by an Applicant for Housing Credit that requires at least 40% of the units in a Housing Credit Development to be both rent restricted and occupied by households whose income is less than or equal to 60% of AMI. This is an irrevocable election made in an Initial Application.

Adaptive Reuse/Conversion – The renovation and reuse of a pre-existing building that has not been used for residential purposes and creates additional affordable housing units. Pre-existing buildings used as hotels or motels are eligible as Adaptive Reuse/Conversion. Adaptive Reuse/Conversion will be evaluated and reviewed as New Construction.

Allocation – the amount of Housing Credit reserved for a development.

AMI – Area Median Income as determined by the U.S. Department of Housing and Urban Development (“HUD”).

Applicable Fraction – The percentage of a building that is treated as low-income use and generally eligible for the LIHC. The Applicable fraction is the smaller of the Unit Fraction or the Floor Space Fraction.

Applicant – An applicant for Low-Income Housing Credit under this QAP that will own the proposed development and to which the credits may be allocated.

Application – See “Initial Application”.

Appraisal – An opinion of value for land and building cost.

Average Income Test – The Average Income Test is a federal minimum set–aside that may be elected by an Applicant for Housing Credit. Under this election, at least 40% of the units in a Housing Credit Development are required to be both rent restricted and occupied by individuals whose incomes do not exceed the imputed income limitation designated by the Applicant. The average of the imputed income limitations designated cannot exceed 60% of AMI. The designated imputed income limitations must be in 10% increments as follows: 20%, 30%, 40%, 50%, 60%, 70%, and 80%. Guidance regarding Average Income Test may be found on the THOMAS Documents Page. This is an irrevocable election made at Initial Application.

Basis Boost – An increase of up to 30% in eligible basis for a building in order to improve the financial feasibility of the building in a difficult to develop area, as determined by THDA in its sole discretion.

Building Permit(s) – Formal approval of building plans by the local government authority or building department certifying that the building plans meet the requirements of applicable codes to construct, enlarge, or alter a building, which allows construction to proceed.

Capital Needs Assessment – See Physical Needs Assessment.

Carryover Allocation Agreement – The document allocating Housing Credit when a development that received a Reservation Notice will not be placed in service in the same year as the Reservation Notice. This document is issued by THDA and extends the required placed–in–service date to the end of the second calendar year after the

year of the Reservation Notice.

Carryover Allocation Application – The application and all related documentation required when a development with a Reservation Notice will not be placed in service in the same year as the Reservation Notice.

Certificate of Occupancy – Formal approval by the relevant local government that a building is suitable for occupancy.

CNI – Choice Neighborhoods Implementation Grants awarded by HUD to PHAs, local governments, or tribal entities to revitalize severely distressed public housing and/or HUD assisted multifamily housing projects.

Code – Internal Revenue Code of 1986, as amended, together with all subsequent tax legislation duly enacted by the Congress of the United States, all United States Treasury Regulations in effect with respect thereto (including regulations first promulgated under previous versions of the Code) and all revenue procedures, revenue rulings, or other published determinations of the Treasury Department or the Internal Revenue Service of the United States.

Competitive Credit Ceiling – the amount of Housing Credit remaining for 2026 after the Permanent Supportive Housing for Homeless Set-Aside established under this QAP have been considered for allocations from the Total Credit Ceiling.

Compliance Period – The period of 15 taxable years, commencing on the first day of the taxable year in which any building that is part of the Housing Credit Development is placed in service or, if deferred by election of the Owner of the Housing Credit Development, the first day of the next calendar year, but only if the building is a qualified low-income building as of the close of the first year of

such period. This definition may be revised under the land use restrictive covenants for a longer duration based on Applicant's election under Section 18 and Section 2.

Concerted Community Revitalization Plan ("CCRP") – A document that assesses the health and potential prosperity of an area less than the entire state, through public interaction and assessment of the physical, social and economic health of the citizenry, businesses, infrastructure, and built environment in the area. A CCRP must contain all of the following:

1. Clearly delineate a targeted area within a local government boundary and where the proposed site sits within that target area;
2. Include housing as a stated goal;
3. Include an assessment of the targeted area's existing infrastructure needs;
4. Designate implementation measures; and
5. Be approved or re-approved by the appropriate local government or entity no earlier than 2016. Local Consolidated Plans for HUD CPD funding are not acceptable.

Conditional 42(m) Letter – A letter issued by THDA to Applicants seeking a determination of 4% Housing Credit in conjunction with uncommitted Multifamily Tax-Exempt Bond Authority.

Construction Schedule – A document showing work to be performed, resources to perform the work, and timeframes in which the work is expected to be performed. The Construction Schedule should reflect all the work associated with delivering a Housing Credit Development on time.

Consultant - A third-party entity that provides consulting services to Housing Credit Development Participants. An entity acting in the capacity of Owner, Developer, or

General Contractor or which provides technical assistance to the Owner, Developer, or General Contractor is considered a Consultant. Consultants include, but are not limited to, construction management consultants, interior design consultants, relocation specialists, tax credit application consultants, resident certification consultants, HOPE VI consultants, etc. All consulting fees are considered part of the calculation of the maximum allowable Developer fee for each Housing Credit Development.

Cost Certification – The certification of actual total development costs for a Housing Credit Development and the amount of Housing Credit eligible basis in the Housing Credit Development upon completion of the development.

Credit Period – The 10–year period over which Housing Credit may be claimed. The Credit Period begins on the first day of the taxable year in which any building that is part of a Housing Credit Development is placed in service or, if deferred by election of the Owner of the Housing Credit Development, the first day of the next calendar year, but only if the building is a qualified low–income building as of the close of the first year of such period.

Cure Notice – The notice sent by THDA to the contact person specified in an Initial Application after completion of Initial Application review to indicate deficiencies in the Initial Application.

Developer - The legal entity designated as the Developer in the Application as well as all persons, affiliates of such persons, corporations, partnerships, joint ventures, associations, or other entities that have a direct or indirect ownership interest in the Developer entity. Material participation (through Placed In Service) is required for all developers and for all entities that receive any portion of the Developer Fee.

Development Team – Any individual or member of the development team including Governors/Directors, Members, and Managers/Officers of the Ownership Entity; Officers, Directors, and Stockholders of the Development Entity; and Officers, Directors, and Stockholders of the Property Management Company.

Difficult Development Area (“DDA”) –Any area designated as such by HUD or as so defined by THDA in accordance with Section 42(d)(5)(B)(v). The list is available here: <https://www.huduser.gov/portal/datasets/qct.html>.

Disability –With respect to an individual, a physical or mental impairment that substantially limits one or more major life activities of such individual; a record of such impairment; or being regarded as having such an impairment. Major life activities include, but are not limited to, caring for oneself, performing manual tasks, seeing, hearing, eating, sleeping, walking, standing, lifting, bending, speaking, breathing, learning, reading, concentrating, thinking, communicating, and working. A major life activity also includes the operation of a major bodily function, including but not limited to, functions of the immune system, normal cell growth, digestive, bowel, bladder, neurological, brain, respiratory, circulatory, endocrine, and reproductive functions. An individual meets the requirement of “being regarded as having such an impairment” if the individual establishes that he or she has been subjected to an action prohibited by law because of an actual or perceived physical or mental impairment whether or not the impairment limits or is perceived to limit a major life activity. An individual will not be regarded as having such an impairment when the impairment is transitory and minor. A transitory impairment is an impairment with an actual or expected duration of 6 months or less. An impairment that is episodic or in remission is a disability if it would substantially limit a major life activity when active. For further definition, please see the Americans with Disabilities Act of 1990, as amended.

Draw Package — Monthly report that minimally includes the following:

1. Request for funds
2. Documentation of change orders
3. Tracking of finances and progress of development
4. Architect inspection report.

Elderly – see definition of Older Persons.

ENERGY STAR – The federal program established by the U.S. Environmental Protection Agency in 1992 under the authority of the Clean Air Act Section 103(g). The program establishes an energy efficient designation that can be achieved. Such designation must be obtained in order to use the ENERGY STAR utility allowances.

Evaluation Notice – A notice provided by THDA to request clarification or additional information during review of a Carryover Allocation Application, requested status report on the development, 10-percent Test, Final Application, quarterly construction report, or certified property management application; during an on-site inspection of the Site during construction, after the buildings are placed in service, or during the term of the Extended Use Agreement; or other compliance concern identified by THDA in its sole discretion. Failure to respond to successive Evaluation Notices by the Final deadline allows THDA, in its sole discretion, to return or reject the application, recapture the allocation, or issue an event of noncompliance under the terms of the Extended Use Agreement.

Executed Notice to Proceed – The Notice to Proceed date marks the beginning of the performance time of the construction contract.

Extended Use Agreement – Also known as the Declaration of Land Use Restrictive Covenants for Low-Income Housing Tax Credits (“LURC”), is the agreement executed

between THDA and Owner. The LURC:

1. Is binding on Owner and all successors of Owner;
2. Requires the Housing Credit Development to comply with the requirements of Section 42, the QAP, the Application, and THDA;
3. Evidences Applicant's federal election and any requirements pursuant to Applicant's scoring elections in the Initial Application;
4. Requires that the applicable fraction for each building for each taxable year during the term of the LURC will not be less than the applicable fraction specified in the LURC;
5. Prohibits the eviction or termination of the tenancy (except for good cause) of an existing low-income resident or any increase in the gross rent with respect to a low-income unit that is not otherwise permitted;
6. Allows individuals who meet the income limitation applicable to the building (whether prospective, present, or former occupants of the building) the right to enforce in any State court the rights under (1) and (2) above;
7. Prohibits the disposition to any person of any portion of the building to which the LURC applies, unless all of the building to which the LURC applies is disposed of to such person;
8. Prohibits the refusal to lease to a holder of a voucher or certificate of eligibility under Section 8 of the United States Housing Act of 1937 because of the status of the prospective resident as such a holder;
9. Is recorded in the real property records of the county in which the Housing Credit Development is located as a restrictive covenant running with the land; and
10. Commences on the first day of the Compliance Period for a term of at least thirty (30) years (the "Extended Use Period").

Existing Multifamily Housing – A multifamily development that will preserve

affordable housing units that are rent and income restricted or, through rehabilitation of units that were not previously affordable, create affordable housing units.

Final Application – The application and all related documentation required when a Housing Credit Development is to be placed in service and for which IRS Forms 8609 are sought.

Final Notice – The THDA notice sent to Applicants, after any required THDA Board of Directors Review Meeting has been held. This notice will summarize the final eligibility and scoring determinations.

Firm 42(m) Letter – A letter issued by THDA to Applicants seeking a determination of 4% Housing Credit in conjunction with a commitment of Multifamily Tax-Exempt Bond Authority.

Floor Space Fraction – The numerator of which is the total floor space of the Low-Income Units in a building and the denominator of which is the total floor space of the residential units (whether or not occupied) in the same building.

Forms and Templates – THDA provided documents that are used in conjunction with Initial, Carryover, or Final Applications and processes.

Forward Reservation – A binding commitment to allocate Housing Credit from a future year to a proposed development.

Hard Cost – Costs directly related to the physical construction of a building in a Housing Credit Development such as construction materials and construction labor.

Housing Credit – Low-Income Housing Tax Credit as described in Section 42 of the Code.

Housing Credit Development – the proposed or existing rental housing development for which Housing Credit has been applied for or allocated.

Housing for the Homeless – housing with support services created to provide permanent supportive housing for Youth Transitioning Out of Foster Care as defined below, or for individuals or families defined and documented as homeless under the “Criteria and Recordkeeping Requirements for Definition of Homelessness” published as HUD Guidance in January 2012, as found on the HUD Exchange website at <https://www.hudexchange.info/homelessness-assistance/coc-esg-virtual-binders/coc-esg-homeless-eligibility/four-categories/>.

Housing for Older Persons – Housing (i) intended for, and solely occupied by, persons age 62 or older; or (ii) where at least 80 percent of the units have at least one occupant that is age 55 years or older per unit, the project publishes and adheres to policies and procedures that demonstrate the intent to operate as “55 or older” housing, and the project complies with HUD’s regulatory requirements for age verification of residents; or (iii) provided for under any state or federal program that HUD has determined is specifically designed and operated to assist older persons (as defined in the state or federal program).

HUD – The United States Department of Housing and Urban Development.

Initial Application – The application submitted by an Applicant seeking an allocation of Housing Credit, including, without limitation, all information and documents entered into THOMAS.

IRS – Internal Revenue Service.

Local Government Notification – Notice provided by THDA, following receipt of Initial Applications, to the chief executive officer (or the equivalent) of the local government in whose jurisdiction a development proposed in an Initial Application is to be located. Such individual will have an opportunity to comment on the development proposed in the Initial Application to be located in the jurisdiction, as required by Section 42(m)(1)(A)(ii).

Low–Income Unit – Any unit in a building if such unit is rent–restricted as provided in Section 42 or this QAP and the individuals occupying such unit meet the income limitation applicable as provided in Section 42 or this QAP.

Market Study – An analysis of the market conditions of supply, demand and pricing for a specific property type in specific areas.

Modification – Any changes to buildings, units, square footage, scoring items, etc. which determine eligibility for an allocation of Housing Credit.

MTBA – Multifamily Tax–Exempt Bond Authority.

NSPIRE - National Standards for the Physical Inspection of Real Estate is HUD’s replacement for the Uniform Physical Condition Standard (“UPCS”) inspection protocol. While NSPIRE is a protocol established by HUD for the purpose of HUD programs, the IRS adopted the same protocol for the purposes of the Housing Credit program incentive in Treasury Regulation Section 1.42-5(d)(2)(ii). THDA will begin utilizing NSPIRE January 1, 2025, unless otherwise directed by Treasury.

Owner’s Annual Certification of Compliance (“OAC”) – An Owner’s required annual certification that the Housing Credit Development was in compliance for the preceding 12-month period. See Section 10.

Owner/Ownership Entity - The single purpose legal entity (e.g. Corporation, Limited Partnership, Limited Liability Partnership) holding title to the Site.

Percentage of Construction Complete –  $(\text{Total Development Cost Incurred as of Report Date} / \text{Total Development Costs}) \times 100$ .

PHA – A public housing authority created under the Housing Authorities Law, Tennessee Code Annotated Section 13–20–101, et seq.

Phase 2 Development – A proposed Housing Credit Development that would add units to a previously awarded Housing Credit Development when the construction of the previously awarded Housing Credit Development is complete and at least 50% of the credit restricted units are leased to income qualified households in compliance

with current rent and income restrictions by the 2026 Competitive Cycle Deadline for Initial Applications.

Placed-in-Service Application – See Final Application.

Physical Needs Assessment – A report prepared by licensed third party provider which contains detailed information about physical needs, deficiencies (including major systems, life safety, and ADA needs) and the capital needs requirements of existing buildings, including a detailed work plan showing all necessary and contemplated improvements and projected costs.

Preliminary Ranking List – A preliminary confirmation of a reservation of Housing Credit from the associated competitive application process.

Pre-Existing Building – A building containing residential rental units previously occupied or approved for occupancy by the applicable authority having jurisdiction.

Qualified Allocation Plan (“QAP”) – The document prepared pursuant to Section 42(m) of the Code that details THDA’s priorities, process, and requirements regarding the Housing Credit program.

Qualified Census Tract (“QCT”) – Any census tract identified as such by HUD. The list is available here: <https://www.huduser.gov/portal/datasets/qct.html>.

Qualified Contract Process (“QCP”) – The process carried out in compliance with elections made in the relevant QAP and THDA’s Qualified Contract Process Guidelines (available here: <https://dogvxws799i6n.cloudfront.net/wp-content/uploads/06.01.20-QUALIFIED-CONTRACT-GUIDELINES-REVISED-FOR-VENDOR-NEEDS.pdf>).

Qualified Nonprofit Organization – An organization that is described in Section 501(c)(3) or (4) of the Code that is exempt from tax under Section 501(a) of the Code, and that meets the additional requirements contained in Section 12 of this QAP.

Qualified Partner – An organization with requisite experience and resources to provide services for the referral of tenants meeting the Youth Aging Out of Foster Care definition of the QAP, or qualifying as homeless under the Housing for the Homeless definition of the QAP, and the provision of supportive services as appropriate for these populations. THDA staff will make the determination at their sole discretion as to whether a partner constitutes a Qualified Partner.

RAD – Rental Assistance Demonstration Program administered by HUD that allows PHAs and owners of other HUD–assisted properties to convert (public housing or other assisted) units from their original sources of HUD financing to project–based Section 8 contracts.

Related Parties – In relation to the Initial Application, any subsequent application or any request for a Modification, related parties include, the Applicant, developer, Owner, entities with commonality of one or more persons with those listed in the Ownership Entity Breakdown, entities with commonality of one or more persons with those listed in the Developer Entity Breakdown, and any of the following:

- a. Any person or entity who has a right to (i) replace the developer, (ii) act as co–developer, (iii) replace any individuals or entities who comprise a developer or co–developer, or (iv) otherwise direct the activities of the developer will be considered a developer for purposes of applying this limit.
- b. Any person or entity who has a right to (i) replace the general partner of the Owner or Applicant,  
(ii) act as co–general partner of the Owner or Applicant, (iii) replace any

individuals or entities who comprise a general partner or co-general partner of the Owner or Applicant, or (iv) otherwise direct the activities of the general partner of the Owner or Applicant will be considered an Owner or Applicant, as the case may be, for purposes of applying this limit.

- c. Any person or entity who has a right to (i) replace the controlling stockholder of the Owner or Applicant, (ii) act as controlling stockholder of Owner or Applicant, (iii) replace any individuals or entities who comprise a controlling stockholder of the Owner or Applicant, or (iv) otherwise direct the activities of the controlling stockholder of the Owner or Applicant will be considered an Owner or Applicant, as the case may be, for purposes of applying this limit.
- d. Any person or entity who has a right to (i) replace the managing member of the Owner or Applicant,  
(ii) act as co-managing member of the Owner or Applicant, (iii) replace any individuals or entities who comprise a managing member or co-managing member of the Owner or Applicant, or (iv) otherwise direct the activities of the managing member of the Owner or Applicant will be considered an Owner or Applicant, as the case may be, for purposes of applying this limit.
- e. Any person who is a signatory or guarantor of construction financing documents, permanent financing documents, and/or equity syndication documents.
- f. This limit will also apply to any person or entity that is related to any person or entity specified above.

Reservation Notice – Notice from THDA to the contact person specified in an Initial Application that Housing Credit may be made available in the competitive Housing Credit allocation process.

Review Notice – The notice sent to the contact person specified in an Initial Application after THDA has reviewed documentation sent in conjunction with a Cure

Notice.

Rural Counties – the counties included in the “Rural/Balance of State” area as outlined in Section 11.

Scattered Site Development – a development located on 2 or more noncontiguous parcels of land.

Site – A parcel of land on which the Housing Credit Development will be developed, described by a unique legal description that will be part of the Carryover Allocation, and encumbered by the LURC. THDA will not allocate Housing Credit based on costs associated with a site, or any portion thereof, which was included in a prior allocation.

Site Control – Documentation submitted in conjunction with the Initial Application, as required by Section 13.A.1, that demonstrates control of the property by the applicant on which the development proposed in the Initial Application is to be located.

Scope of Work – A general description of the construction/rehabilitation work and estimate of cost that is expected to be performed under a construction contract. The Scope of Work should contain any milestones, reports, deliverables, and end products expected to be provided. The Scope of Work should contain a timeline for all deliverables.

Section 42 – Section 42 of the Code, as amended, together with all subsequent legislation duly enacted by the Congress of the United States affecting Section 42, all United States Treasury Regulations in effect with respect thereto (including regulations first promulgated under previous versions of the Code) and all revenue procedures, revenue rulings, or other published determinations of the Treasury

Department or the IRS applicable to Section 42.

Significant Adverse Event (“SAE”) – An occurrence of noncompliance (curable or incurable), program fraud or misrepresentation, or an act that adversely conflicts with THDA’s mission as described in Section 5 of this QAP.

Special Housing Needs – Housing needs served by housing that has been constructed or rehabilitated with special features (e.g. location, design, layout, or on-site services) to help people live at the highest level of independence in the community. For example, the unit may be adapted to accommodate special physical or medical needs; or provide on-site services such as staff support for older persons, individuals with mental health issues, developmental, or other social needs.

Supportive Services – Furnished through a contract with supportive service providers to provide Supportive Services, appropriate for a particular special needs population, under a planned program of services. In the case of persons with disabilities or housing for older persons, such services may be designed to enable residents of a Housing Credit Development to remain independent and avoid placement in a hospital, nursing home, or intermediate-care facility.

Supportive Services for Older Persons – Must include at least two of the following services: social and recreational programs, continuing education, information and counseling, recreation, homemaker, outside maintenance and referral services, an accessible physical environment, emergency and preventive health care programs, congregate dining facilities, or transportation to facilitate access to social services and facilities available to them.

Tennessee Growth Policy Act – Tennessee Code Annotated Section 6-68-101 et seq. that requires growth plans approved by the Tennessee Advisory Commission on Intergovernmental Relations. Information available here: <https://www.tn.gov/tacir/tennessee-county-growth-plans.html>.

Total Credit Ceiling – The maximum amount of Housing Credit THDA may allocate in a given year, which includes Housing Credit returned pursuant to Section 24.

Total Development Cost – The total of actual costs associated with new construction or rehabilitation development activities, as determined to be reasonable by THDA, in its sole discretion.

THOMAS Documents Page – A web page with necessary forms, templates, guidance, calendar, and links that are used in all application processes.

THOMAS – The Tennessee Housing Online Management and Application System.

THOMAS User Manual – THDA provided document that gives guidance for use of THOMAS.

Unit Fraction – The numerator of which is the number of Low–Income Units in a building and the denominator of which is the number of residential rental units (whether or not occupied) in the same building.

Youth Transitioning Out of Foster Care – youth that meet the following criteria:

- a) Were emancipated to adulthood from state custody at or after their 18th birthday OR are currently participating in Extension of Foster Care Services OR have exited Extension of Foster Care Services;

- b) Were in Department of Children’s Services (DCS) custody for at least 1 year;
- c) Were or will be emancipated or will have left Extension of Foster Care Services within 12 months of application;
- d) Are not receiving other housing assistance including, but not limited to:
  - 1) Housing placement through DCS;
  - 2) Long-term housing provided by a social service organization for a free or reduced rate;
  - 3) Housing Choice Voucher, Continuum of Care Rental Assistance, Veterans Affairs Supportive Housing (VASH) Rental Assistance;
- e) Are a citizen and have a valid social security number;
- f) Have an income at or below 60% of Area Median Income as adjusted for household size.

Zoning – Written documentation from the appropriate local government authority demonstrating that current zoning and other local land use regulations permit the development as proposed: or that no such regulations currently apply to prevent the development proposed in the Initial Application.

### **Section 3: THOMAS and Initial Application Submission Requirements**

#### **A. Applications**

1. All applications involving Housing Credit, including Initial Applications, must be submitted electronically through THOMAS. If THDA determines that THOMAS malfunctions in a way that renders applicants unable to submit applications on-line, THDA will provide alternative instructions via e-mail BLASTS and THDA website postings. THDA reserves the right to identify in-progress applications and extend application deadlines to meet THOMAS's operational capacities.
2. Initial Applications proposing a combination of new construction **and** Existing Multifamily Housing will be scored as new construction if the majority of the Low-Income units are new construction or will be scored as Existing Multifamily Housing if the majority of the Low-Income units are Existing Multifamily Housing.
3. Initial applications proposing scattered sites must include a Site Plan Map of all the residential and common area buildings including all the common area amenities that are clearly labeled showing the distance from the furthest point of the amenities.
4. Initial applications proposing scattered sites must include a detailed narrative including all the addresses of the proposed sites, number of units and bedroom mix in each development, and type of development.
5. All fees must be received by THDA via a wire transfer in the amounts and by the deadlines specified in Section 4 of this QAP. An Initial Application is not complete unless and until the required fee is received by THDA.

#### **B. Supporting Documents**

1. Supporting documents required as part of an Initial Application or subsequent application must be uploaded into THOMAS as specified in the

THOMAS User Manual. Supporting documents must be no older than 6 months prior to the applicable application deadline, unless otherwise specified in the QAP.

2. The THOMAS Documents Page contains Forms and Templates for required third party reports.
3. THDA will not accept cost certifications, market studies, physical needs assessments and/or appraisals prepared by parties connected with any person or entity involved with the Development Team or Related Parties, as determined by THDA, in its sole discretion.

## Section 4: Program Fees

### A. Effective Date

The fee schedule reflected below shall be in effect as of January 1, 2026.

### B. Wiring instructions

**All fees must be paid via an electronic wire.**

Applicants are required to send the wire confirmation to [thomas@thda.org](mailto:thomas@thda.org).

Table 4–1: Wiring Instructions Format	
Bank:	US Bank
ABA:	064000059
BNF:	THDA Clearing Housing
BNF A/C:	151203673398
BNF ADDRESS:	502 Deaderick Street Andrew Jackson Building, Third Floor Nashville, TN 37243
OBI:	Housing Credit + TN ID Number(s).  Applicants may send one wire to cover multiple applications however, applicants must enter the applicable TN ID Number(s) in the OBI field on the wire.

### C. Fee Schedule

Fees are not refundable and may not be applied to other types of fees or fees related to a different application, unless THDA determines that circumstances beyond the Applicant's anticipation or control are present.

The following fees shall apply:

#### Table 4-2: Fee Schedule

- Initial Application Fee (1-4 Units) is \$395 and is due when Initial Application is Submitted
- Initial Application Fee (5-50 Units) is \$1,595 and is due when Initial Application is Submitted
- Initial Application Fee (51-100 Units) is \$2,210 and is due when Initial Application is Submitted
- Initial Application Fee (101+ Units) is \$40 per unit and is due when Initial Application is Submitted
- Deadline Extension Fee (1-5 days) is \$500 and is due when Request is made
- Deadline Extension Fee (6-30 days) is \$200 per day and is due when Request is made
- Deadline Extension Fee (Over 30 days) is \$6,000 and is due when Request is made
- Reservation Fee, determined at 6.25 percent of the total amount of competitive Housing Credit approved by THDA. Amount is calculated by THDA and due when Reservation Notice is accepted.
- 42(m) Letter Fee, determined at 6.25 percent of the total amount of noncompetitive Housing Credit requested by the Applicant. Amount is calculated by THDA and due when a Firm Commitment is accepted.
- Modification Fee, equal to the greater of \$750 or 0.625 percent of the annual Housing Credit specified in the Reservation Notice. Amount is calculated by THDA and due when a Request is made.
- Project Based Section 8 Subsidy Layering Review Fee is \$5,000 and due when Request for SLR is submitted

- 8609 Amendment Fee is \$50 per form, with a \$250 Minimum and due when Request is made.
- Monitoring Fee is \$600 per Low Income Unit and due when Final Application is submitted
- Income-Averaging Monitoring fee is \$600 per Low Income Unit and due when Final Application is submitted
- Income- Averaging Monitoring Fee is \$1,200 per Housing Credit unit and due when Final application is submitted
- Compliance Re-Inspection fee is \$200 per unit and due when Request is made
- Owner’s Annual Certification Extension Fee (max 30 days) is \$250 and due Prior to submission deadline
- Owner’s Annual Certification (“OAC”) Late Fee is \$500 per month and is due upon submission of OAC
- Utility Allowance Estimate Fees (Utility Company Estimate Methodology) is \$200 and is due when Request is made
- Utility Allowance Estimate Fees (Energy Consumption Model Methodology) is \$200 and is due when Request is made
- Utility Allowance Estimate Fees (Agency Estimate) is \$200 and is due when Request is made

**Section 5: Development Team Members and Eligibility Thresholds**

THDA prefers Development Teams that have successful experience in Tennessee with the THDA Housing Credit Program. Such experience is evidenced by successful construction, rehabilitation, and placing in service of a recent Housing Credit Development, maintaining a good track record in the on-going operations of the Housing Credit Development, and providing the capacity to sustain the Housing Credit Development in the ever changing regulatory and rental market. Consequently, an Initial Application for Housing Credit is ineligible under this QAP when any member of the Development Team or any individual who is identified in

the Initial Application as a member of the Development Team have, with respect to any prior Housing Credit Development, incurred and failed to cure any and all major SAE(s) that have been identified since January 1, 2020 or are otherwise ineligible based on any other event listed under Other Ineligibility (below) as of the Initial Application date.

**A. Major SAEs**

Major SAEs include, without limitation, situations in which any individual involved in the Initial Application was part of a prior Housing Credit Development to which any of the following apply:

1. The general partner/managing member/sole stockholder being removed from the ownership entity of a prior Housing Credit Development;
2. Returning credits due to the development not being able to meet its targeted placed-in-service deadline and requesting THDA to approve and make an Exchange of Credit Allocation. (No Major SAE will be imposed when THDA determines that an Exchange was necessitated by circumstances beyond the Applicant's anticipation or control);
3. An uncured event of default under the Section 1602 or Tax Credit Assistance Program;
4. A Fair Housing Act violation, which resulted in a finding of discrimination by an adverse final decision from HUD, an equivalent state or local fair housing agency, or a federal or state court;
5. The Housing Credit Development was foreclosed, where such foreclosure occurred after December 31, 2020, including a deed in lieu of foreclosure;
6. Submitting to the IRS an IRS Form 8609 that was not created by THDA in an effort to claim Housing Credit or submitting to the IRS an IRS Form 8609 which has been altered or contains information inconsistent with the IRS Form 8609 created by THDA in an effort to claim Housing Credit; or
7. Failure to meet the federal placed-in-service deadline for a development

that received Competitive or Noncompetitive Housing Credit.

**B. Other Ineligibility**

Housing Credit Initial Applications are ineligible if any of the following apply:

1. Any individual involved in the Initial Application has any one of the following:
  - a. A felony conviction of any type on or after January 1, 2016; or
  - b. A fine, suspension, or debarment involving financial or housing activities on or after January 1, 2021, imposed by any federal agency; or
  - c. A current bankruptcy or a bankruptcy discharged on or after January 1, 2022, or any organization or entity in which the individual had significant control currently is in bankruptcy or had a bankruptcy discharged on or after January 1, 2022; or
  - d. Individual bankruptcy of a member of the board of directors of an entity that is, or is wholly controlled by, a government entity will not be grounds for ineligibility provided that the individual certifies that he/she will not have substantial decision-making authority with regard to the proposed development; or
  - e. Any suspensions of required state licenses (Tennessee or any other state) on or after January 1, 2016.
2. An individual who is a member of the Development Team identified in the Initial Application and who is involved with another Housing Credit Development in Tennessee that has participated in the Qualified Contract Process since January 1, 2024.
3. An individual who is a member of the Development Team identified in the Initial Application and who is involved with a pre-2026 Housing Credit Development with a first allocation of Competitive Housing Credit in Tennessee; prior to THDA issuing IRS Form(s) 8609 for that development.

4. An individual who is a member of the Development Team identified in the Initial Application, where such individual was involved in an application that received a commitment of MTBA during 2024, but such MTBA bonds were not issued and sold by the expiration date (original or extended) of the MTBA Firm Commitment Letter and the MTBA Firm Commitment Letter was not released as described in Section 10-H of the 2025 MTBA Program Description.
5. If any of the following are true regarding an individual who is a member of the Development Team identified in the Initial Application for any development receiving an allocation of Housing Credit after December 31, 2015:
  - a. They were involved in a pre-2026 Housing Credit Development with an accepted Reservation Notice, but the proposed Housing Credit Development failed to meet the federal allocation timeframes and did not obtain a Carryover Allocation Agreement; or
  - b. They were involved in a pre-2026 Housing Credit Development with a fully executed Carryover Allocation Agreement, but the proposed Housing Credit Development failed to meet the federal allocation timeframes and did not obtain IRS Form(s) 8609; or
  - c. They were involved in a pre-2026 Housing Credit Development for which THDA issued IRS Form(s) 8609, but the Housing Credit Development failed to meet the minimum set-aside test for low-income tenants as specified in the LURC by the end of the first year of the Credit Period; or
  - d. They were involved in a pre-2026 Housing Credit Development that THDA determined to be in violation of the requirements of the applicable QAP regarding developer or related party issues; or
  - e. They were involved in a pre-2026 Housing Credit Development that involved a “broker” who did not remain involved in the Initial

Application through the closing of permanent financing for the Housing Credit Development; or

- f. They were involved in a pre-2026 Housing Credit Development that did not meet the requirements of the applicable QAP regarding submission of permanent financing documentation to THDA; or
  - g. They were involved in a pre-2026 Housing Credit Development that involved a “consultant” who was determined to be a signatory of construction financing, permanent financing or equity syndications documents or provided a guaranty in connection with construction financing, permanent financing or equity syndication; or
  - h. They were involved in a pre-2026 MTBA Application that received a firm commitment of bond authority but failed to meet the established deadline for issuance and sale of the bonds. Voluntary withdrawal of a Multifamily Tax Exempt Bond Authority Application in accordance with all applicable program requirements will not cause ineligibility; or
- 6. The Initial Application is deemed ineligible pursuant to any other provisions of this QAP.
  - 7. An individual involved in the Initial Application was involved with another Housing Credit Development at the time the development was placed in “No Further Monitoring” status by THDA and the project remains in “No Further Monitoring” Status. “No Further Monitoring Status” was a status attributed to Housing Credit Developments that are outside of the Section 42 defined Compliance Period that failed to respond to and/or cure notices for monitoring reviews, submit annual compliance reports, or comply with program requirements for 180 days from the date THDA provided the notice of noncompliance. Ineligibility hereunder continues until the noncompliance is cured or the LURC expires.
  - 8. There is pending or threatened litigation with regard to (i) an entity or

individual that is involved in the Initial Application; (ii) an entity or individual that will be involved in the Ownership Entity; or (iii) any other aspect of the proposed project, where THDA determines that the existence of such could be detrimental to the success or feasibility of the project. This does not include cases merely arising from opposition to the development of the Project.

**C. Requests for Relief**

If an Initial Application is submitted and one or more uncured SAEs is attributable to an individual involved with such application, the Initial Application is subject to disqualification at the determination of the Executive Director, who shall notify the THDA Board of Directors of such action. The THDA Board of Directors retains the authority to revisit such determination.

**D. Minor SAEs**

Minor SAEs are events that, cumulatively, may affect the eligibility of an Initial Application. Multiple Minor SAEs indicate consistent problems and poor performance in Housing Credit Developments in which members of the Development Team are involved.

Effective January 1, 2020, THDA will track Minor SAEs as they occur in the development and ongoing operations of Housing Credit Developments by Development Team and by individuals identified as members of the relevant Development Team.

As THDA becomes aware of Minor SAEs, THDA will notify the Development Team. The Minor SAE(s) reflected in the notice may or may not be curable. **Cured** Minor SAE(s) under this section reflected in an Evaluation Notice may impact Initial Application scoring for a period of time beginning with the effective date of the notice and ending **the later of:** (i) two years after the

effective date of the notice (as applicable) or (ii) when the Minor SAE is cured. **Incurable or uncured** Minor SAE(s) under this section reflected in a notice may impact Initial Application scoring for a period of time beginning with the effective date of the notice and ending two years or five years after the effective date of the notice (as applicable).

Minor SAEs will be counted relative to the Development Team, not individual members. The cumulative total of Minor SAEs will determine the Development Team Track Record points.

Minor SAEs include, without limitation, any of the following that occur with respect to any Housing Credit Development in Tennessee:

1.
  - a. Defaulting on loan payments, unpaid property taxes, or having arrearages of at least three months on any loan for any Housing Credit Development; unpaid property taxes will not constitute a Minor SAE if acceptable evidence of active appeal is provided;
  - b. Failing to utilize all listed funding sources in the amount or under the terms described in the Initial Application until any Housing Credit Development is placed in service, unless THDA has been advised of the change in funding source and agreed to the change;
  - c. Failing to maintain and operate amenities and services specified in the Initial Application throughout the term of the LURC;
  - d. Failing to convert construction loan financing to permanent loan financing within 6 months of THDA issuance of IRS Form 8609;
  - e. Making changes to the Housing Credit Development ownership entity without THDA approval;
  - f. Failing to fulfill commitments made in any application, including without limitation those for scoring points in the Initial Application

(except for changes approved by THDA, in its sole discretion);

- g. Failing to correct outstanding noncompliance issues within the applicable correction period;
- h. Failing to respond to written requests from THDA for information and/or documentation by the prescribed deadline in any such written request.

## **Section 6: Mandatory and Threshold Requirements**

All documentation must be in full force and effect and fully executed. To be eligible, Initial Applications for new construction or rehabilitation (with or without acquisition) must meet all of the following requirements, as applicable, as determined by THDA, in its sole discretion.

### **A. Mandatory Requirements**

1. **Site Control** – To be eligible, an Initial Application must demonstrate control of the Site. A copy of any one of items a.- d. below must be part of the Initial Application:
  - a. Recorded instrument of conveyance (warranty deed, quitclaim deed, trustee deed, court order) evidencing title to the Site vested in (A) the currently existing Ownership Entity identified in the Initial Application or (B) a person or entity identified in the Initial Application as the general partner or managing member of the Ownership Entity to be formed, along with a draft of the document that will convey title to the Ownership Entity;
  - b. Acceptable evidence demonstrating the ability to acquire the Site through the power of eminent domain by (A) the currently existing Ownership Entity identified in the Initial Application or (B) a person or entity identified in the Initial Application as the general partner or managing member of the Ownership Entity to be formed;
  - c. Contract for sale or a contract for a 50-year ground lease, which contract must show that the ground lease, when executed, will meet the requirements specified in item e. below, executed by (A) the owner of record of the Site and (B) the currently existing Ownership Entity identified in the Initial Application or a person or entity identified in the Initial Application as the general partner or managing member of the Ownership Entity to be formed. The contract must extend at least six months from the applicable 2026 Deadline for Initial Applications (see Table 21-1 or

Section 6 of the 2026 MTBA PD) with an extension to MTBA closing/Carryover site control demonstration; or

- d. An option to purchase or an option for a 50-year ground lease, which option must show that the ground lease, when executed, will meet the requirements specified in item e. below, executed by (A) the owner of record of the Site and (B) the currently existing Ownership Entity identified in the Initial Application or a person or entity identified in the Initial Application as the general partner or managing member of the Ownership Entity to be formed. The option must extend at least six months from the applicable Deadline for Initial Applications (see Table 21-1 or Section 6 of the 2026 MTBA PD) with an extension to MTBA closing/Carryover site control demonstration.
- e. A ground lease for the Site must have a minimum term of 50 years with no provisions for termination or reversion prior to the expiration of the extended use period as defined in Section 42(h)(6)(D). Proposed developments which are the subject of a Payment In Lieu of Taxes (“PILOT”) agreement may be exempt from this minimum term requirement subject to THDA’s review of and satisfaction with the terms of the PILOT.
- f. Assignments of contracts or options will not be accepted unless the underlying contract or option that meets the requirements set forth above is provided as well.
- g. The legal description included with the documentation pursuant to Site Control requirements and the legal description included with the documentation pursuant to Underlying Seller Authority requirements must be consistent with each other. All documentation must be in full force and effect, fully executed, and include a correct legal description for the Site.
- h. If the legal descriptions required pursuant to Site Control requirements and Underlying Seller Authority Site Control requirements do not match

exactly, the Applicant may submit an attorney certification stating that the legal description included with the documentation pursuant to Section 6.A.1. and the legal description included with the documentation pursuant to Section 6.A.2. both refer to the same Site.

- i. The purchase price must be clearly stated in the documentation submitted pursuant to Site Control requirements.
- j. If the Site identified in an Initial Application under this QAP includes land for which the purchase cost has already been taken into account in connection with a prior allocation of Tax Credits, no cost for the purchase of the land will be permitted in connection with the Site identified in the Initial Application under this QAP.

**2. Site Control – Underlying Seller Authority Documentation (required in addition to Site Control as described in Section 6.A.1).**

- a. A commitment for title insurance evidencing that title to the Site is vested in the person or entity who executed the document required for Site Control as owner, which must include a valid legal description of the Site. The commitment for title insurance must be dated no more than 60 days prior to the Initial Application Deadline and the proposed insured must be listed as the Ownership Entity or the general partner or managing member of the Ownership Entity to be formed;
- b. All documentation must be in full force and effect, fully executed, and include a correct legal description for the Site.
- c. The legal description included with the documentation pursuant to Site Control requirements and the legal description included with the documentation pursuant to Underlying Seller Authority requirements must be consistent with each other.
- d. If the legal descriptions required pursuant to Site Control requirements and Underlying Seller Authority do not match exactly, the Applicant may submit a an attorney certification stating that the legal description

included with the documentation pursuant to Section 6.A.1. and the legal description included with the documentation pursuant to Section 6.A.2. both refer to the same Site.

3. **Zoning** – Evidence that Sites are currently zoned for the proposed Development must be demonstrated through either:

a. A letter from the local zoning administrator (or chief elected official in localities without a zoning administrator) identifying the Development and containing all four (4) of the following:

1) location of the Site(s) (e.g. address or street crossings); and 2) The current zoning and any special use designations; and 3) A description of the Development (including number of units, proposed use, and construction type i.e. townhome, midrise elevator, etc. ); and 4) A statement that the current zoning will permit the proposed Housing Development;

OR

b. A letter from the local zoning administrator (or chief elected official in localities without a zoning administrator) identifying the Development and containing all four (4) of the following:

1) The location of the Site(s) (e.g. address or street crossings); and 2) A description of the Development (including number of units, proposed use, and construction type, i.e. townhome, midrise elevator, etc.); and 3) A overview of the Zoning/PUD approval process and timing; and 4) Assurance that the Zoning/PUD will be reviewed in a timely manner, including any available dates so as it is complete by time of award process;

OR

c. A letter from the chief elected official identifying the Development and stating that there are no zoning regulations in place.

4. **Minimum Score** - Achieve a minimum score as specified in Section 18 of this QAP, or Section 6 of the 2026 MTBA PD, as determined by THDA, in its sole discretion.

5. **Market Study** - is included, acceptable, accurately reflects the Development presented in the Initial Application, and is performed and prepared by an independent third party in accordance with the Market Study Guidelines included on the THOMAS Documents Page.
6. **Appraisal** - If land or building acquisition costs are part of the development costs, include an acceptable Appraisal of the land and/or building acquisition that is performed and prepared by an independent third party in accordance with the Appraisal Guidelines included on the THOMAS Documents Page.

## **B. Threshold Requirements**

1. Eligible Initial Applications must meet all of the following requirements:
  - a. Be a qualified low-income housing development, containing qualified low-income buildings and low-income units;
  - b. Submit a Physical Needs Assessment, if applicable, in accordance with the THDA Physical Needs Assessment Guidance on the THOMAS documents page;
  - c. Comply with the Fair Housing Act, as applicable;
  - d. Comply with the Fair Housing Act design and construction requirements for units that are considered “covered multifamily dwellings” designed and constructed “for first occupancy” after March 13, 1991, using one of HUD’s recognized safe harbors;
  - e. Comply with the Americans with Disabilities Act (ADA), as applicable; and
  - f. Comply with all applicable local building codes or State adopted building codes in the absence of local building codes.
2. **Site Utilities** - Include documentation in the Initial Application from the relevant local jurisdiction verifying availability of electricity, water, sewer, and, if applicable, natural gas. Septic fields are prohibited for buildings with more than 4 units. If an on-site treatment facility is proposed, the Initial Application must include a separate financing commitment for the

development and maintenance of the facility.

3. **Financial Feasibility** - Include documentation demonstrating that the development is financially feasible. The ownership entity for the proposed Development is structured as a single purpose entity and must be able to clearly show that the Development is financially sustainable based on income from operations. The sources and uses must be available at the time of Application. Lender and Investor LOIs should demonstrate that there will be no shortfall of funds during the construction period; and permanent finance is structured and included. THDA may require documentation not specifically included in the minimum documentation requirements to verify the reasonableness of operating costs, as determined by THDA, in its sole discretion.
4. **Financial Pro-forma** - Include a 30-year pro-forma for the proposed development in the Initial Application.
5. **Minimum Set-Aside Election** - Include one of the following minimum set-aside elections in the Initial Application, except for an Initial Application that proposes rehabilitation of a prior Housing Credit Development:
  - a. The 20/50 Test; or
  - b. The 40/60 Test; or
  - c. The Average Income Test.

An Initial Application that proposes rehabilitation of a prior Housing Credit Development must elect the minimum set-aside elected in the Initial Application for the prior Housing Credit Development, except that where the 40/60 Test was initially selected, an Applicant may, concurrent with its submission of the Initial Application, submit a waiver request to THDA informing them of the development's intent to use of the Average Income Test.

6. **Certifications and Disclosures.**

- a. Include an executed Statement of Application and Certification in the form shown on the Template provided in THOMAS and in accordance with Guidelines on the THOMAS Documents Page.
  - b. Include an executed Certificate Regarding Eligibility for Low–Income Housing Credit in the form shown on the Template provided in THOMAS and in accordance with the Guidelines on the THOMAS Documents Page.
  - c. Include a Certificate Regarding Acquisition Housing Credit (if Acquisition Housing Credit is requested) in the form shown on the Template provided in THOMAS and in accordance with Guidelines on the THOMAS Documents Page.
  - d. Include a certificate that Owner will comply with Affirmatively Furthering Fair Housing Marketing requirements and provide THDA its Marketing Plan in its Carryover Allocation Application or prior to issuance of a MTBA Firm Commitment Letter.
  - e. Include all required Disclosure Forms in the form shown on the Template provided in THOMAS and in accordance with Guidelines on the THOMAS Documents Page
7. **Organizational Breakdowns.**
- a. Include a THDA Organizational Ownership Breakdown in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.
  - b. Include a THDA Organizational Developer Breakdown in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.

## **Section 7: New Construction and Rehabilitation Minimum Requirements**

Owners shall develop all New Construction and Rehabilitation units in compliance with THDA's "Minimum Design Standards for the Rehabilitation and New Construction of Single Family and Multifamily Housing Units," as may be amended, which can be found on THDA's website at:

[https://dogxws799i6n.cloudfront.net/wp-content/uploads/THDA-Design-Standard-w-Rehabilitation-Standards-Rev.-12.23-2023-12-27-140320\\_swrf.pdf](https://dogxws799i6n.cloudfront.net/wp-content/uploads/THDA-Design-Standard-w-Rehabilitation-Standards-Rev.-12.23-2023-12-27-140320_swrf.pdf).

Other methods of construction and design may be acceptable on a case-by-case basis, and goals and requirements may be approved for waivers. All requests for waivers should be discussed with multifamily staff prior to application.

## **Section 8: Construction Review Process**

### **A. Construction Overview**

THDA will conduct a preconstruction meeting with the ownership entity, developer, architect, and general contractor after closing of the equity syndication and construction financing. Documentation in a form and with substance specified by THDA must be uploaded into THOMAS. Guidance may be found on the THOMAS Documents Page. The architectural drawings and specifications, as approved by the syndicator and lender, shall be submitted into THOMAS within five (5) days after closing. If rehabilitation of Existing Multifamily Housing or adaptive reuse is proposed, the scope of work must also be submitted in THOMAS within five (5) days after closing. The scheduling of the preconstruction meeting shall not take place until the information is submitted to THDA using THOMAS. **THDA does not approve or provide any representations or warranties in connection with architectural drawings, specifications or other documents submitted in connection with the construction review process described in this Section.**

### **B. Preconstruction Meeting**

The purpose of the preconstruction meeting is to outline basic responsibilities and duties of the various parties throughout the construction process in relation to the Housing Credit Program.

1. For developers with no previous Housing Credit program experience, a full preconstruction meeting must take place.
2. Developers with previous Housing Credit program experience may request a limited preconstruction meeting.
3. THDA shall determine, in its sole discretion, whether the preconstruction meeting will be full or limited.

**Preconstruction meeting scheduling should not delay construction progress.**

### **C. Construction Inspections and Reporting**

After the preconstruction meeting has been conducted, construction reporting and periodic construction site visits by THDA are required.

1. The following required documents shall be submitted in THOMAS prior to construction site visits:
  - a. Executed Notice to Proceed
  - b. Building Permits (if not required, the applicable local official must submit a letter verifying that building permits are not required).
  - c. Construction Schedule with anticipated benchmarks
2. During the construction process, THDA will inspect the work progress monthly, or as otherwise determined by THDA to be necessary, and conduct periodic site inspections for compliance with THDA requirements based on the Percentage of Construction Complete as reported in THOMAS.
3. Monthly executed draw packages and quarterly construction progress reports are required and shall be submitted in THOMAS.
4. Updated construction schedule and scope of work shall be submitted based on the Schedule of Evaluation Notices and Deadlines if requested by THDA:

Table 8–1: Schedule of Evaluation Notices and Deadlines

Evaluation Notice	Deadline for Response
1	5 business days
2	2 business days
Final	1 business day

### **D. Completion of Construction Documentation**

The following items shall be uploaded to THOMAS following completion of construction and before the final construction inspection is scheduled:

1. Architect Certification regarding:
  - a. Compliance with applicable building codes; and
  - b. Compliance with all federal accessibility requirements including without limitation, ADA and Fair Housing Act requirement; and
  - c. Compliance with NSPIRE, and
  - d. Compliance with all state requirements.
2. Certificate of substantial completion issued by the architect; and
3. Certificate of Occupancy for each building (if not required, applicable local official must submit a letter verifying this information), and
4. Final Draw Package.

**E. Final Construction Inspection**

Once construction is 100% complete, all documents have been submitted in THOMAS, all threshold requirements in the QAP and items selected for points in the Initial Application are complete, a final construction inspection will be conducted to determine compliance with THDA requirements and NSPIRE.

## **Section 9: Final or Placed in Service Process**

### **A. Timeframes for Final Application Submission**

After all units in a development are placed in service, the completion of construction documentation shall be submitted into THOMAS. THDA will then schedule the final construction inspection referenced in Section 8–E.

### **B. THOMAS Final Application Submission Requirements**

Following notice from THDA regarding a satisfactory final construction inspection, a Final Application may be submitted through THOMAS. THDA maintains an open cycle for the submission of Final Applications in THOMAS. The Final Application must be entered into THOMAS with required supporting documents. The Final Application must include, without limitation, the following items:

1. An executed Final THDA Statement and Application in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.
2. An executed Final THDA Accountant Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.
3. An executed Final THDA Eligibility Certificate in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.
4. An executed Final THDA Syndication Letter Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.
5. An executed Final THDA Eligibility Opinion Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.

6. An executed Final THDA Acquisition Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page, if applicable.
7. An executed Final THDA Nonprofit in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page, if applicable.
8. An executed Final THDA Ownership Organizational Breakdown Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page, if applicable.
9. An executed Final THDA Developer Organizational Breakdown in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page, if applicable.
10. An executed Final THDA Disclosure Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page, if applicable.
11. An executed Final THDA Disclosure Exemption Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page, if applicable.
12. An executed copy of the most recent partnership agreement or operating agreement, if not already provided.
13. A 30-year pro-forma for the development in the Final Application
14. An executed Recorded Copy of THDA Land Use Restrictive Covenant in THOMAS.
15. An executed Permanent Financing Documentation in THOMAS, if applicable
16. An executed THDA Certification of Outstanding MTBA in the form shown on the template in accordance with the Guidelines on the THOMAS Documents Page, if applicable.

**C. Final Application Review Process**

During the review of the Final Application, THDA will issue Evaluation Notices

that may request additional documentation and/or information for purposes of clarification of eligibility, scoring and financial feasibility. Evaluation Notices will be issued in the following manner:

Table 9–1: Schedule of Evaluation Notices and Deadlines

Evaluation Notice	Deadline for Response
1	5 business days
2	2 business days
Final	1 business day

THDA will not issue IRS Form(s) 8609 if all conditions contained in Evaluation Notices are not fully satisfied. The deadline specified in the final Evaluation Notice is the date upon which Housing Credit may be recaptured by THDA if the conditions related to the deadline are not met. Upon notification, the Housing Credit referred to in the Carryover Allocation Agreement or Section 42(m) Letter are not available for the development and will be made available to other qualified developments.

**D. Final Allocation of Housing Credit**

THDA will make a final allocation of Housing Credit and will issue IRS Form(s) 8609 after satisfactory review of the Final Application and supporting documents are completed. **The amount of Housing Credit allocated to a development at placed in service may be less than, but will not be more than, the amount reserved in the Reservation Notice, or the amount referenced in the Section 42(m) Letter, or the amount allocated in the Carryover Allocation Agreement. THDA reserves the right to make downward adjustments to the final amount of Housing Credit allocated based on the information submitted, QAP requirements, and Section 42 requirements.**

**E. Timely Return of Signed 8609s**

Owner must submit its executed 8609s to THDA within 30 calendar days after

its first-year tax returns are due to the IRS.

**F. Submission of Permanent Financing Documents**

THDA must receive a copy of the promissory note and recorded deed of trust for permanent financing of the development in THOMAS within sixty (60) days of the date of recording of the deed of trust. Failure to provide such documentation shall be deemed an event of noncompliance. THDA reserves the right to issue revised IRS Form(s) 8609 following receipt of the promissory note and recorded deed of trust if the terms of the promissory note or deed of trust vary from the terms specified in the Final Application.

## **Section 10: Compliance Requirements and Monitoring Process**

The following compliance requirements and monitoring process apply to all buildings placed in service in Tennessee under this QAP. Owners are responsible for complying or ensuring compliance of the Housing Credit Development with Section 42, relevant regulations, the LURC, and the applicable QAP throughout the term of the LURC. THDA's obligation to monitor the compliance of such does not make THDA or the State of Tennessee liable for an Owner's noncompliance. THDA carries out its monitoring responsibilities in accordance with Section 42, relevant regulations, the applicable QAP and Initial Application submitted thereunder, and the LURC. THDA also relies on guidance from the IRS, including Revenue Procedures, Revenue Rulings, and other similar guidance. The requirements under this Section may be modified as federally required.

- A. Owner's Annual Certification of Compliance ("OAC"). Each year, during the term of the LURC, Owners shall certify, under penalty of perjury, by the deadline established by THDA, that, for all times during the prior calendar year, that the Housing Credit Development was in compliance with Section 42, relevant regulations, the Initial Application, the LURC, and the applicable QAP(s) and that all of the following were true. If the Owner cannot certify to one or more of the above items, a detailed explanation of the situation must be provided to THDA with the OAC.
  1. The units were leased according to the Owner's THDA-approved Affirmatively Furthering Fair Housing ("AFFH") Marketing Plan. All Owners must certify at Initial Application to affirmatively further fair housing through an AFFH Marketing plan, provide the AFFH Marketing Plan as part of the Carryover Allocation Application, and revise it yearly, as needed. The AFFH Marketing Plan must include:
    - a. Owner's analysis to understand the development's housing market demographics for the area;

- b. Identified impediments to fair housing choice within such area and underserved populations or populations that are least likely to apply to live in the development;
  - c. Marketing efforts Owner has developed to take appropriate actions to overcome the effects of any identified impediments to ensure a diverse applicant pool and resident population. Such marketing efforts should be beyond usual methods of advertising; and
  - d. Owner's plan to maintain records reflecting the analysis and actions under the Affirmative Fair Housing Marketing Plan. The following resources may assist in the development of an Affirmative Fair Housing Marketing Plan:
    - (i) 24 CFR Part 200 Subpart M -- Affirmative Fair Housing Marketing Regulations
    - (ii) <https://www.irs.gov/pub/irs-drop/rr-16-29.pdf>
    - (iii) <https://public-inspection.federalregister.gov/2021-12114.pdf>
    - (iv) <https://www.hud.gov/hudclips/forms> (hud.gov)
2. There were no findings of discrimination under the Fair Housing Act, 42 U.S.C. 3601–3619 for the Housing Credit Development;
  3. The Housing Credit Development met the minimum election set–aside requirements of the appropriately selected test (i.e. 40/60 Test, 20/50 Test, or Average Income Test) consistent with the irrevocable election made at the time of the Initial Application under the relevant QAP;
  4. There was no change in the applicable fraction of any building in the Housing Credit Development or that there was a change and a description, satisfactory to THDA, of that change;
  5. The Owner's files contain annual Household Income Certifications from each low–income household and documentation to support that certification at initial occupancy and at each subsequent year during the term of the LURC;

6. Proper approval for the applicable utility allowances used to determine rent as outlined in Paragraph M of this Section.
7. THDA's restrictions on rent increases were followed. An Owner may only raise a tenant's amount of rent:
  - a. At lease renewal with a 90-day notice; or
  - b. Mid-lease term, if the HUD-published income limits would raise the amount of rent an Owner is allowed to charge. However, the (i) the lease must allow for such increase mid- term (ii) the tenant must be given a 90-day notice, and (iii) the tenant must be given the opportunity to break the lease and relocate if the household does not agree to the increase in rent.
8. All units in the Housing Credit Development were for use by the general public;
9. Each building in the Housing Credit Development is suitable for occupancy, taking into account NSPIRE standard and local health, safety, and building codes (or other habitability standards) and the state or local government unit responsible for making local, health, safety, or building code inspections did not issue a violation report for any building or low-income unit in the development;
10. There has been no change in the eligible basis of any building in the Housing Credit Development or, if there was a change, the nature of the change;
11. All resident facilities included in the eligible basis of any building in the Housing Credit Development, such as a swimming pool, other recreational facilities, and parking areas, were provided on a comparable basis, without charge, to all residents of the Housing Credit Development;
12. If a low-income unit became vacant during the year, reasonable attempts were made to rent that unit or the next available unit of comparable or smaller size to households having a qualifying income before any units in the Housing Credit Development were rented to households not having a

- qualifying income and while the unit was vacant, no units of comparable or smaller size were rented to households not having a qualifying income;
13. If the income of a household occupying a low-income unit in the Housing Credit Development increased above the applicable income limit, the next available unit of a comparable or smaller size was rented to a household having a qualifying income;
  14. A LURC was in effect, and included a provision that an Owner cannot refuse to lease a unit in the Housing Credit Development to an applicant because the applicant holds a voucher under Section 8 of the United States Housing Act of 1937, 42 U.S.C. 1437f;
  15. All low-income units in the Housing Credit Development were used on a non-transient basis, meaning the initial lease term was at least six (6) months, except for transitional housing for the homeless or single-room occupant units rented on a month-by-month basis;
  16. If the Owner received Housing Credit from the Non-Profit Set-Aside, the "Qualified Non-profit Organization" materially participated (regular, continuous and substantial on-site involvement) in the on-going operation of the development; and
  17. All requirements associated with items for which points were taken at the time of Initial Application were met.
  18. All required Tenant Notices were provided.
    - a. Owners shall notify every tenant household that if the LURC is terminated due to foreclosure or a qualified contract that, for a period of three years, beginning on the date of the termination, (i) eviction or termination of the tenancy of an existing tenant is prohibited, other than for good cause and (ii) increase in the gross rent is prohibited, except in accordance with Section 42(g); and
    - b. If the LURC is expiring naturally, Owners shall notify tenants of the upcoming expiration one (1) year before such expiration.

19. Owner listed all vacancies for every property they own that receives any type of THDA funding at TNHousingSearch.com.

B. Physical Reviews and Desk Reviews.

1. THDA must conduct physical, on-site inspections of all buildings in a Housing Credit Development (“Physical Reviews”) and must conduct desk reviews of the low-income certification files of a Housing Credit Development (“Desk Review”) by the end of the second calendar year following the year the last building in a Project is placed in service and then at least once every 3 years thereafter.
2. For each Housing Credit Development that is due to be reviewed in a particular year, THDA must conduct physical reviews for 20% of the low-income units in the Housing Credit Development, rounded up to the nearest whole number of units or the Minimum Unit Sample Size set for Housing Credit Development that is due to be reviewed in a particular year, THDA must also conduct desk reviews for an additional 20% of the low-income units in the Housing Credit Development, rounded up to the nearest whole number of units or the Minimum Unit Sample Size set forth in the table to 26 CFR 1.42-5(c)(2)(iii), whichever is less.
3. The Physical Reviews and Desk Reviews could be conducted on different units and may be conducted on different days or times.
4. Desk Reviews may be performed at THDA’s offices.
5. Owners must have a provision in each lease that allows 24-hour notice to tenants of an upcoming THDA inspection. If an Owner fails to timely notify tenants of an upcoming physical inspection, the inspection must be rescheduled and Owner shall pay a Compliance Reinspection Fee.

C. Owners shall submit the OAC and required tenant data submission for the Desk Review via THOMAS or THDA’s online system within the timeframe specified by THDA. The Owner must designate an Administrator in THOMAS.

This Administrator must be an individual approved by THDA within the Organization Structure and may not be an outside individual.

- D. THDA will provide prompt written notice to an Owner if any of the following occur:
1. THDA does not receive the OAC by the specified deadline.
  2. THDA does not receive or is not permitted to inspect household income certifications, supporting documentation, or rent records.
  3. THDA does not receive executed 8609s within 30 calendar days of the Owner's deadline to file its first-year tax return.
  4. THDA discovers by inspection, review or in some other manner that the Housing Credit Development is not in compliance with Section 42, the relevant regulations, the LURC, or the applicable QAP.
- E. Owners shall pay fees, as determined by THDA, to cover the administrative expenses of monitoring compliance and other expenses incurred in carrying out its duties as the Housing Credit Agency, including but not limited to, reasonable fees for legal and professional services.
- F. Owners have thirty (30) days to provide missing documentation or to correct noncompliance (the "Correction Period"). The Correction Period begins on the date of THDA's written notice to the Owner specifying the missing documentation or the noncompliance via regular mail or via e-mailed to the address specified for the Owner or Owner's contact in the files held by THDA. The Correction Period may be extended up to an additional 150 days for a total Correction Period not to exceed six (6) months upon a showing of good cause by the Owner, all as determined by THDA in its sole discretion. Notwithstanding the foregoing, THDA will not grant extensions for items that are immediate health and safety issues.

- G. Owners must mitigate all emergency health and safety items immediately and file a written report and documentation with THDA proving the items have been mitigated. Owners must provide the report and documentation of the action taken to complete the mitigation within 3 business days of the emergency instance (the “Health and Safety Correction Period”).
  
- H. THDA will file an IRS Form 8823, Low–Income Housing Credit Agencies Report of Noncompliance, with the IRS to show noncompliance or failure to certify compliance no later than 45 days after the end of the Correction Period and no earlier than the end of the Correction Period, whether or not the noncompliance or failure to certify compliance is corrected.
  
- I. THDA has the right to inspect any Housing Credit Development at any time during the term of the LURC, including, but not limited to, on–site inspections and review of all records relating to compliance with, without limitation, Section 42 requirements, Treasury regulations, the applicable QAP, and the LURC. Owner shall promptly deliver copies of household certifications and supporting documentation as may be required by THDA.
  
- J. Owners shall submit, not less than annually during the term of the LURC, information concerning the race, ethnicity, family composition, age, income, use of rental assistance under Section 8(o) of the United States Housing Act of 1937 or other similar assistance, disability status, and monthly rental payments of households residing in the development in a form, with substance, and with timing as THDA may require.
  
- K. Property Management Certification. Every property management team, whether Owner-managed or not, must receive and maintain a current, valid, certification through the THDA Property Management Compliance

Certification Program for the term of the LURC. More information is available here: <https://thda.org/rental-housing-partn/housing-credit-compliance/>.

L. Compliance Training for Owners.

1. For Housing Credit Developments involving new construction, Owners and the management entity shall send attendees (at least one representative per entity) to the Owner's compliance training sessions provided by THDA within the 12 months prior to the issuance of the IRS Form 8609. Only attendees who are listed on the Organization Chart submitted in THOMAS or who are employees of the Owner may meet this requirement.
2. For Housing Credit Developments involving rehabilitation, Owners and the management entities shall send attendees to the Owner's compliance training sessions provided by THDA prior to the placed-in-service date for the development. Only attendees who are listed on the Organization Chart submitted in THOMAS or who are employees of the Owner may meet this requirement.
3. If there is a change in the ownership entity during the term of the LURC, then the new Owner and management entity shall send attendees to the Owner's compliance training session as scheduled and provided by THDA. Only attendees who are listed on the Organization Chart submitted in THOMAS or who are employees of the Owner may meet this requirement.

M. Determination of Utility Allowance. Utility Allowances must be determined in accordance with Treasury Regulation 1.42-10.

1. If the cost of any utility (other than telephone, cable television, or Internet) for a residential rental unit is paid directly by the tenant(s), and not by or through the Owner of the Housing Credit Development, the gross rent for that unit includes the applicable utility allowance determined in accordance with 1.42-10. For purposes of the preceding sentence, if the

cost of a particular utility for a residential unit is paid pursuant to an actual-consumption submetering arrangement within the meaning of paragraph (e)(1) of 1.42-10, then that cost is treated as being paid directly by the tenant(s) and not by or through the Owner.

2. All Utility Allowances must be rounded up to the nearest whole dollar amount.
3. Mandatory Utility Allowance Methodologies.
  - a. Rural Housing Service (“RHS”) Assisted Building. If a building receives assistance from the RHS, the applicable utility allowance for all rent-restricted units in the building is the utility allowance determined under the method prescribed by RHS for the building (whether or not the building or its tenants also receive other state or federal assistance).
  - b. Buildings with RHS Assisted Tenants. If any tenant in a building receives RHS rental assistance payments (RHS tenant assistance), the applicable utility allowance for all rent-restricted units in the building (including any units occupied by tenants receiving rental assistance payments from HUD) is the applicable RHS utility allowance.
  - c. Buildings Regulated by HUD. If neither a building nor any tenant in the building receives RHS housing assistance, and the rents and utility allowances of the building are regulated by HUD (HUD-regulated buildings), the applicable utility allowance for all rent-restricted units in the building is the applicable HUD utility allowance.
  - d. Tenants Receiving HUD Rental Assistance. If a building is neither an RHS-assisted nor a HUD-regulated building, and no tenant in the building receives RHS tenant assistance, the applicable utility allowance for any rent-restricted units occupied by tenants receiving HUD rental assistance payments (HUD tenant assistance) is the applicable Public Housing Authority (“PHA”) utility allowance established for the Section 8 Existing Housing Program.

4. Elective Utility Allowance Methodologies. If none of the above situations apply, an Owner may request to utilize one of the following utility allowance methodologies, however, a **\$200 fee will be charged** to cover THDA's review for such requests, except for the Applicable PHA Utility Allowance Methodology. Each request must include a cover letter that identifies the development name, TN Number, method requested for each type of utility, and number of units categorized by the type of unit (apartment, townhome, etc.), bedroom sizes (1 bedroom, 2 bedrooms, etc.), square footage of the applicable units, and, if applicable, the proposed estimated rates for those units per type of utility (electric, gas, water, sewer, trash). All required documents must be sent to [TNCompliance@thda.org](mailto:TNCompliance@thda.org). No elective methodology, other than the Applicable PHA Utility Allowance, may be elected until at least twelve (12) months' worth of actual consumption data is available.
  - a. Applicable PHA Utility Allowance. The PHA utility allowance from the local housing authority that administers Section 8 vouchers for the area in which the Housing Credit Development is located. Copies of the PHA utility allowance must be uploaded to THOMAS during the application process and annually. These also may be requested during monitoring reviews. If THDA is the local PHA, the HUD Utility Schedule Model is the method utilized to calculate the estimate and can be found on THDA's website.
  - b. Utility Company Estimate. Any interested party (including a Housing Credit Development tenant, an Owner, or THDA) may obtain a local utility company estimate for a unit, as outlined below:
    - (i) The estimate must be in writing and outline the estimated cost of that utility for a unit of similar size and construction for the geographic area in which the Housing Credit Development is located.

- (ii) In the case of deregulated utility services, the interested party is required to obtain an estimate only from one utility company even if multiple companies can provide the same utility service to a unit. However, the utility company must offer utility services to the building in order for that utility company's rates to be used in calculating utility allowances.
  - (iii) The estimate should include all component deregulated charges for providing the utility service.
  - (iv) Unless the parties agree otherwise, costs incurred in obtaining the estimate are borne by the initiating party.
  - (v) The interested party that obtains the local utility company estimate must retain the original and furnish a copy to the Tenant, Owner, and THDA, as applicable.
  - (vi) The Owner must make copies of the estimate available to all tenants in the building.
- c. Agency Estimate.
- (i) THDA will take into account, among other things, local utility rates, property type, climate and degree-day variables by region in Tennessee, taxes and fees on utility charges, building materials, and mechanical systems.
  - (ii) An Owner must provide a completed THDA Utility Allowance Certification Form for each type of utility being considered. Such form will outline all requirements of the Owner in requesting this methodology.
- d. HUD Utility Schedule Model. A building owner may calculate a utility estimate using the "HUD Utility Schedule Model" that can be found on the Low-Income Housing Tax Credits page at <https://www.huduser.gov/portal/resources/utlallowance.html> (or successor URL). Utility rates used for the HUD Utility Schedule Model

must be no older than the rates in place 60 days prior to the date Owner submits its request to THDA.

- e. Energy Consumption Model. An Owner may calculate utility estimates using an energy and water and sewage consumption and analysis model (energy consumption model).
  - (i) The energy consumption model must, at a minimum, take into account specific factors including, but not limited to, unit size, building orientation, design and materials, mechanical systems, appliances, characteristics of the building location, and available historical data.
  - (ii) The utility consumption estimates must be calculated by a properly licensed engineer or other qualified professional. The qualified professional and the building Owner must not be related within the meaning of section 267(b) or 707(b). If a qualified professional is not a properly licensed engineer and if the Owner wants to utilize that qualified professional to calculate utility consumption estimates, then the Owner must obtain approval from THDA.
  - (iii) THDA may approve or disapprove of the energy consumption model or require information before permitting its use.
- f. Additional Requirements.
  - (i) The twelve-month data provided to substantiate the proposed estimated utility allowance, must be no older than 60 days prior to THDA's receipt of the request for the use of a specific methodology.
  - (ii) THDA's receipt of a request starts a 90-day review period (the 90-day Period'). Such request must include proof that, prior to the submittal of the request to THDA, the Owner provided each tenant with notice of the same proposed estimate it provided to

THDA in its request.

- (iii) THDA will attempt to provide an approval or denial of the request within thirty (30) calendar days of its receipt of the request.
- (iv) Regardless of when THDA completes its review and provides an Owner with an approval letter, the new utility allowance must not be implemented prior to the expiration of the 90-Day Period.
- (v) THDA may ask for additional information or require that the utility allowance be recalculated to address shortcomings. If deficiencies are identified, they must be resolved before an approval notice will be provided to the Owner.
- (vi) If THDA's review results in a change to a utility allowance, the new utility allowance must be used to compute gross rents for the very next time rent is due under a lease and tenants must be given notice of such change in the gross rent 30 days prior to such due date.
- (vii) The year following an approval of a methodology, the Owner shall review the basis on which the utility allowances were established and complete and submit a certification to THDA that the basis has not changed.
- (viii) Biennially (every other year), the Owner must reapply for an elected methodology following the steps above.

5. Actual-Consumption Submetering Arrangements. Must possess all of the following attributes:

- a. The utility consumed in the unit meets one of the following:
  - (i) The utility is purchased from or through a local utility company by the Owner (or its agent or other party acting on behalf of the Owner); or
  - (ii) The utility is not purchased from or through a local utility company and is produced from a renewable source, as defined at

26 CFR 1.42-10(e)(1)(i)(C) and (D).

- b. The tenants in the unit are billed for, and pay the Owner (or its agent or other party acting on behalf of the building owner) for, the unit's consumption of the utility.
- c. The billed amount reflects the unit's actual consumption of the utility. In the case of sewerage charges, however, if the unit's sewerage charges are combined on the bill with water charges and the sewerage charges are determined based on the actual water consumption of the unit, then the bill is treated as reflecting the actual sewerage consumption of the unit; and
- d. The rate at which the building owner bills for the utility satisfies the following requirements:
  - (i) To the extent that the utility consumed is described in paragraph 5.a.(i) of this section, the utility rate charged to the tenants of the unit does not exceed the rate incurred by the building owner for that utility; and
  - (ii) To the extent that the utility consumed is described in paragraph 5.a.(ii) of this section, the utility rate charged to the tenants of the unit does not exceed the highest rate that the tenants would have paid if they had obtained the utility from a local utility company. In determining whether a rate satisfies the preceding sentence, a building owner may rely on the rates published by local utility companies.
- e. Administrative fees. If the owner charges a unit's tenants a fee for administering an actual- consumption submetering arrangement, the fee is not considered gross rent for purposes of Section 42(g)(2). The preceding sentence, however, does not apply unless the fee is computed in the same manner for every unit receiving the same submetered utility service, nor does it apply to any amount by which

the aggregate monthly fee or fees for all of the unit's utilities under one or more actual-consumption submetering arrangements exceed the greater of—

- (i) Five dollars per month;
- (ii) An amount (if any) designated by publication in the Internal Revenue Bulletin (see § 601.601(d)(2)(ii) of Title 26, Chapter I of the Code of Federal Regulations); or
- (iii) The lesser of— (A) The dollar amount (if any) specifically prescribed under a State or local law; or (B) A maximum amount (if any) designated by publication in the Internal Revenue Bulletin (see § 601.601(d)(2)(ii) of Title 26, Chapter I of the Code of Federal Regulations).

N. Record Retention. Owners shall maintain records for each qualified low income building in the Housing Credit Development for each year for the term of the LURC sufficient to meet the requirements of 26 CFR Section 1.42–5(b). Any household records or other records maintained in an electronic format must be accessible to THDA at THDA's request.

O. Change in Ownership Entity, General Partner, or Managing Member. In the event of a sale, transfer, or exchange of a Housing Credit Development or any change with respect to the general partner/managing member of the ownership entity (including, without limitation, sale of any or all general partner interests, removal of any general partner/managing member, or admission of any general partner/managing member), the Owner shall:

1. Obtain THDA's permission before such action occurs;
2. Complete THDA's Organizational Breakdown Form;
3. Provide a new Organizational Chart;

4. Provide notarized THDA Disclosures Forms for every new individual added to the structure;
5. THDA may require the proposed new Owner or proposed new general partner/managing member of the ownership entity to meet with THDA staff. This is in addition to the training requirements above;
6. Depending on the change, attend compliance training. These requirements do not apply when a development is sold following the completion of the QCP when THDA has not identified a purchaser; and
7. If the change is a change in the Ownership Entity, execute and record an Assignment & Assumption Agreement for the LURC (and all loan documents for TCAP and 1602).

P. VAWA. The Violence Against Women Reauthorization Act of 2013 (“VAWA”) added the Housing Credit program to the housing programs covered by VAWA. Even though the act stated that nothing in the act shall be construed to disqualify an owner, manager, or other individual from participating in or receiving the benefit of the tax credit program due to noncompliance with VAWA, Owners may face other liability if the project is not in compliance. For example, a violation of VAWA arising from an eviction may violate the good cause eviction requirement or violations may put the tax credits in jeopardy as being seen as a violation of fair housing. VAWA was recently amended under The Violence Against Women Reauthorization Act of 2022. Therefore, Owners should implement the requirements of VAWA, including, but not limited to, providing Form HUD-5380 to all existing tenants, when an applicant is denied admission, when an applicant is admitted, and when a tenant receives any notice of eviction or termination of assistance.

**PART II: COMPETITIVE ALLOCATIONS ONLY**

**Section 11: Limits on Housing Credit Allocations**

THDA will only allocate an amount of Housing Credit necessary for the financial feasibility of a development and its viability as a qualified low-income housing development in accordance with Section 42(m)(2). THDA may reject or require modifications to Initial Applications for Housing Credit when THDA determines that the proposed development is not financially feasible or does not need Housing Credit. THDA may also reserve or allocate an amount of Housing Credit less than the amount requested in an Initial Application, in a Carryover Allocation Application, or in a Final Application. THDA's determination under Section 42(m)(2) shall not be construed to be a representation or warranty by THDA as to the financial feasibility, viability, or lack thereof, of any development.

**A. Annual Ceiling**

The methodology to determine the annual Total Credit Ceiling is contained in Section 42(h)(3)(C).

**B. Set-Asides and Available Housing Credit Amounts**

1. Non-Profit Allocations – **THDA's obligation to allocate no less than 10% of the Total Credit Ceiling to Qualified Nonprofit Organizations is intended and expected to be met through the normal course of the competition established through this Qualified Allocation Plan. THDA reserves the right to prioritize and make allocations of Housing Credit to Qualified Nonprofit Organizations, regardless of category or ranking, as may be needed to meet the requirements of Section 42(h)(5).**
2. Permanent Supportive Housing for Homeless Set-Aside – up to \$1,000,000.00 of the **Total Credit Ceiling** may be allocated to developments supporting homeless populations as described in Section 14 of this QAP.

### C. General Priority Categories

1. New Construction – The balance of the **Competitive Total Credit Ceiling minus \$7.2 million** (\$3.6 million each) reserved for the Existing Multifamily Housing and PHA General Priority Categories will be allocated to developments involving new construction.
2. Existing Multifamily Housing – No more than **\$3.6 million** of the **Competitive Credit Ceiling** will be allocated to developments that include rehabilitation of Existing Multifamily Housing.
3. PHA General Priority Category – No more than **\$3.6 million%** of the **Competitive Credit Ceiling** will be allocated to developments involving a PHA that meets the requirements of Section 17 of this QAP.

### D. New Construction Regional Housing Needs Areas


Under the New Construction General Priority Category, THDA will allocate Housing Credit to developments proposing new construction within each of the following six regional housing needs areas, and to the number of developments within each of them, as outlined below and on the following map:

- West Tennessee Urban Area (up to 2 developments will be awarded)
- Middle Tennessee Urban Area (up to 2 developments will be awarded)
- Southeast Tennessee Urban Area (1 development will be awarded)
- East Tennessee Urban Area (1 development will be awarded)
- Northeast Tennessee Urban Area (1 development will be awarded)
- Rural/Balance of State (up to 2 developments will be awarded)

In the event credits remain in the Total Credit Ceiling after awards have been allocated as outlined above, THDA will make an allocation of credits to the next highest scoring Initial Application, regardless of location in the state, for which sufficient credits remain to make a full award.



MAP 11-1



**E. Annual Housing Credit Limit**

Initial Applications are not eligible for annual Housing Credit in excess of \$1,800,000.00.

**F. Total Development Costs**

1. THDA will determine which new construction proposals show total development cost (“TDC”) per unit amounts outside one standard deviation from the average TDC per unit of development proposals across the state, and require applicants for all such proposals to provide explanations for the deviation.

Inability to explain the costs satisfactory to THDA staff, in its sole discretion, may result in disqualification of the application.

2. THDA will evaluate total development costs and may adjust costs for reasonableness, necessity, and eligibility or disqualify applications not reflecting an efficient use of Housing Credits.

**G. Developer Fees and Consultant Fees Limits**

1. The combined total of Developer and Consultant fees that may be included in the determination of the amount of Housing Credit for a particular development cannot exceed 15% of that portion of THDA determined eligible basis attributable to acquisition (before the addition of the developer and consultant fees), and cannot exceed 15% of that portion of THDA determined eligible basis attributable to new construction or to rehabilitation (before the addition of the developer and consultant fees). Construction Advisory or Construction Supervision fees listed separately from the maximum allowed Contractor Fees will be considered as a Consultant Fee.
2. If the Developer and contractor are related persons as defined in Section 42(d)(2)(D)(iii), then the combined total of developer fees, consultant fees, and contractor profit, contractor overhead, and general requirements, that may be included in the determination of the amount of Housing Credit for a particular development, cannot exceed 15% of THDA determined eligible basis of that portion of the development attributable to acquisition (before the addition of the fees), and cannot exceed 25% of that portion of THDA determined eligible basis attributable to new construction or to rehabilitation (before the addition of the fees).

**H. Limit on Contractor Fees, Profit, Overhead and General Requirements**

1. The total contractor fees, including contractor profit, contractor overhead and general requirements, shall not exceed 14% of total site work costs plus cost of accessory buildings plus either new building hard costs or rehabilitation hard costs, as determined by THDA, broken down as follows:

Table 11–3: Contractor Fees, Profit, Overhead and General Requirements  
Limitations

Fee Description	Fee Amount
Contractor Profit	<=6 percent
Contractor Overhead	<=2 percent
Contractor General Requirements (incl payment and perf bonds)	<=6 percent
Total Contractor Fees	<=14 percent

2. If the Developer and contractor are related persons as defined in Section 42(d)(2)(D)(iii), then the combined total for (i) contractor profit, overhead, and general requirements; (ii) developer fees; and (iii) consultant fees that may be included in the determination of the amount of Housing Credit for a particular development cannot exceed 15% of THDA determined eligible basis on that portion of the development attributable to acquisition (before the addition of the fees), and cannot exceed 25% of that portion of THDA determined eligible basis attributable to new construction or to rehabilitation (before the addition of the fees).

**I. Basis Boost**

A “Basis Boost” of no more than 30% will be available to all applicants and awarded at THDA’s discretion.

**J. Applying Limits**

In applying the limits specified in this QAP, THDA will consider, without limitation, the physical location of developments; the relationships among Owners, Developers, contractors, Consultants, management agents, other development participants, and Related Parties; the structure of financing; and any other information which THDA, in its sole discretion, may deem necessary.

## Section 12: Non-Profit Allocations

To be eligible and considered for Housing Credit via a Non-Profit Allocation, an Initial Application must contain information satisfactory to THDA demonstrating that the Owner for the development proposed in the Initial Application involves a Qualified Nonprofit Organization. An Initial Application must meet all requirements in this QAP for an eligible Initial Application and be subject to all applicable limits.

To be a Qualified Nonprofit Organization, ALL of the following requirements must be met. Please note that ONLY successful non-profit applications awarded allocations under this sections and actually identified as such by THDA staff will be required to maintain non-profit compliance throughout the compliance period:

- A. The organization must be a bona fide non-profit organization, as evidenced by the following:
  1. The organization must be an entity that is described in Section 501(c)(3) or (4) of the Code that is exempt from tax under Section 501(a) of the Code;
  2. The organization must be organized and existing in the State of Tennessee or if not organized and existing in Tennessee, then the organization must be organized and existing in another state and must be qualified to do business in Tennessee;
  3. The organization must: (i) not be formed by one or more individuals or for-profit entities for the principal purpose of being included in the Non-Profit Set-Aside; (ii) not be controlled by a for-profit organization; and (iii) not have any staff member, officer or member of the board of directors who will materially participate, directly or indirectly, in the proposed development as or through a for-profit entity; and
  4. The organization must be engaged in the business of developing **AND** constructing or rehabilitating low-income rental housing in Tennessee and must have been so engaged on or after January 1, 2021.

- B. The organization must, prior to the reservation of Housing Credit: (i) own all of the general partnership interests of the ownership entity of the development; or (ii) own, alone or with other Qualified Nonprofit Organizations that meet all of the requirements of this Section, 100 percent of the stock of a corporate ownership entity of the development; or (iii) own, alone or with other Qualified Nonprofit Organizations that meet all of the requirements of this Section, 100 percent of the stock, 100 percent of the partnership interests, or 100 percent of the membership interests of an entity that is the sole general partner or sole managing member of the ownership entity of the development proposed in the Initial Application. This structure must be maintained for the duration of the LURC.
- C. The Qualified Nonprofit Organization must materially participate (regular, continuous and substantial on-site involvement) in the development and operation of the development throughout the Section 42 defined Compliance Period.
- D. To demonstrate eligibility, ALL of the following must be submitted in THOMAS as part of the Initial Application:
1. A copy of the IRS determination letter clearly stating the organization's status as a 501(c)(3) or 501(c)(4) entity; and
  2. A copy of the most recent partnership agreement or operating agreement or draft partnership agreement or operating agreement for the Ownership Entity; and
  3. Certificate of Existence
    - a. If organized and existing under the laws of the State of Tennessee, a certificate of existence from the Tennessee Secretary of State's Office dated not more than thirty (30) days prior to the date of the Initial

Application.

- b. If organized and existing under the laws of another state, a certificate of existence from the secretary of state of the state in which the organization was organized and is existing, together with other documentation from such secretary of state indicating that the organization is in good standing under such laws and a certificate of authorization from the Tennessee Secretary of State indicating that the organization is qualified to do business in Tennessee, all dated not more than thirty (30) days prior to the date of the Initial Application; and
4. An executed Certificate Regarding Qualification for the Non-Profit Set Aside, the form of which is located on the THOMAS Documents Page.

### **Section 13: Permanent Supportive Housing for Homeless Set-Aside**

To be eligible for the Permanent Supportive Housing for Homeless Set-Aside, an Initial Application must contain information demonstrating that the development proposed is designed to provide Housing for Homeless as defined in the QAP. An Initial Application must meet all requirements in this QAP for an eligible Initial Application. 100% of the units in the proposal must be for permanent supportive Housing for Homeless. Applicants **must** include at the time of Initial Application a proposed partnership with a qualified partner for the provision of supportive services.

- A. New Construction OR Rehabilitation.
  
- B. Maximum annual Housing Credit set-aside of \$1M.
  
- C. Proposals which will provide housing to Persons with Disabilities must include documentation satisfactory to THDA, in its sole discretion, that the housing meets the qualities of settings that are eligible for reimbursement under the Medicaid home and community-based services that were established by the Centers for Medicare and Medicaid Services (CMS) in the final rule dated January 16, 2014:  
<https://www.federalregister.gov/documents/2014/01/16/2014-00487/medicaid-program-state-plan-home-and-community-based-services-5-year-period-for-waivers-provider>. The documentation must demonstrate that the proposed housing meets certain qualifications, including:
  1. The setting is integrated and supports full access to the greater community;
  2. Is selected by the individual from among setting options;
  3. Ensures individual rights of privacy, dignity, and respect, and freedom from coercion and restraint;
  4. Optimizes autonomy and independence in making life choices; and
  5. Facilitates choice regarding services and who provides them.
  6. Additionally, for provider owned or controlled residential settings, the

following additional requirements apply:

- (i) The individual has a lease or other legally enforceable agreement providing similar protections;
- (ii) The individual has privacy in their unit including lockable doors, choice of roommates, and freedom to furnish or decorate the unit;
- (iii) The individual controls his/her own schedule, including access to food at any time;
- (iv) The individual can have visitors at any time; and,
- (v) The setting is physically accessible.

D. A reservation funded under this set-aside will not cross-count against other set-asides or general priority categories.

E. While it is unlikely that more than one reservation can be funded under this set-aside, THDA will fund as many qualifying proposals as can be fully funded according to the final THDA ranking.

F. If no qualifying applications are received under the set-aside, or if the set-aside is not able to be fully utilized, any balance will return to the Competitive Credit Ceiling.

#### **Section 14: New Construction General Priority Category**

To be eligible for a Housing Credit allocation under the New Construction General Priority Category, an Initial Application must propose new construction of multifamily housing, meet all requirements in this QAP for an eligible Initial Application, and meet all applicable limits.

New Construction General Priority Category developments may be located in a QCT.

**Section 15: Existing Multifamily Housing General Priority Category**

To be eligible for a Housing Credit allocation under Existing Multifamily Housing General Priority Category, the Initial Application must propose rehabilitation (with or without acquisition) of Existing Multifamily Housing, meet all requirements in this QAP for an eligible Initial Application, and be subject to all applicable limits. The proposed Existing Multifamily Housing development is not required to have existing income or rent restrictions.

Following rehabilitation, 100% of the units must be subject to income and rent restrictions.

- A. A development may be located in a QCT.
  
- B. A preference will be given to Initial Applications proposing a development covered by a CCRP, taking into account score and other limits in this QAP.

## Section 16: PHA General Priority Category

To be eligible for the PHA General Priority Category, an Initial Application must contain information demonstrating that the development proposed in the Initial Application involves a qualified PHA. An Initial Application must meet all requirements in this QAP for an eligible Initial Application, and be subject to all applicable limits.

- A. To be considered a qualified PHA, the following requirements must be met in connection with an Initial Application:
  - 1. The PHA must materially participate (regular, continuous and substantial on-site involvement) in the development and operation of the development throughout the term of the LURC; and
  - 2. The PHA must be acting solely within the geographic area of its jurisdiction; and
  - 3. The PHA must submit an executed Certificate Regarding Qualification for the Public Housing Set Aside, the form of which is found on the THOMAS Documents Page; and
  - 4. The PHA must provide a copy of the most recent partnership agreement or operating agreement or draft partnership agreement or operating agreement for the Ownership Entity.
  
- B. Within the PHA General Priority category, the Project Location Score (see Section 16.A.1) will not apply. In the event of a tie, the tie breaker methodology found in Section 18.F. of this QAP shall apply.
  
- C. Awards from the PHA General Priority category shall be made in the following order:
  - 1. **All CNI Initial Applications** in order of ranking.
  - 2. Highest ranking **new construction** Initial Application that proposes utilizing RAD in connection with a development **located in a CCRP**, taking into account score and other limits in this QAP.
  - 3. Highest ranking **rehabilitation** Initial Application that proposes utilizing

RAD in connection with a development **located in a CCRP**, taking into account score and other limits in this QAP.

4. Highest ranking Initial Application that proposes utilizing RAD, but the proposed development is located outside a CCRP, taking into account score and other limits in this QAP.
5. Highest ranking Initial Application that proposes a development that will be owned and operated by a PHA, but does not involve RAD and is not located in a CCRP, taking into account score and other limits in this QAP.
6. After completing steps 2 through 4 above, THDA will continue making allocations to eligible Initial Applications in the order of steps 1 through 3 above until the point is reached where there is insufficient Housing Credit remaining in the PHA General Priority Category to make another complete allocation.

D. To be considered for the PHA RAD preference, the following requirements must be met:

1. The PHA must submit the Form of Letter from PHA Executive Director Regarding the Rental Assistance Demonstration (RAD) Program (found on the THOMAS Documents Page); and
2. The PHA must submit a copy of the Commitment to enter Housing Assistance Payments (CHAP).

E. To be considered for PHA RAD with CCRP preference, the PHA must submit a copy of the Concerted Community Revitalization Plan.

F. Initial Applications in the PHA General Priority Category may be located in a QCT.

G. An Applicant must indicate whether the Initial Application is to be considered in the PHA General Priority Category or in the Existing Multifamily Housing

General Priority Category. The Initial Application will only be considered in the category selected. No cross counting is allowed.

## **Section 17: Initial Application Scoring**

### **A. New Construction Only:**

The scoring criteria in this section are not intended to allow an Applicant to claim the maximum 100 points. An eligible Initial Application must have a minimum score of **65 points** (minimum score for Initial Applications in the PHA General Priority Category is **52 points**) to be eligible. THDA will determine the score during the scoring review process.

1. **Housing Credit Development Location:** **up to 4 points**  
Initial Applications proposing developments located in areas with the greatest Regional Housing Needs Score (see Section 11 and [Proposed Siting Model for New Construction - 2026 QAP Public](#)). **This criterion does not apply within the PHA General Priority Category. See Section 12.B. Please additionally note that consistent with the legend associated with the map found at “Proposed Siting Model for New Construction - 2026 QAP Public,” priority areas identified by cities will automatically qualify for 4 points.**
  
2. **Meeting Housing Needs:** **up to 6 points**
  - a. Initial Applications in which the 40/60 Test is elected may earn up to 5 points by setting aside an additional percentage of units for households with incomes no higher than 50% of AMI with rents maintained at or below the 50% AMI maximums.
  - b. Initial Applications that elect the 20/50 Test may earn up to 5 points by setting aside an additional percentage of units for households with incomes no higher than 40% of AMI with rents maintained at or below the 40% AMI maximums.
  - c. Units to be occupied by households with a Section 8 Housing Choice

Voucher count towards this requirement.

- d. Initial Applications in which the Average Income Test is elected are ineligible for these points.

Table 17–1: Units Restricted to Serve Lower Income Populations

% of Units Restricted (rounded up to next whole unit number) Available	Points
40/60 Test serving 50 percent households	
At least an additional 5 percent at 50 % AMI	1
At least an additional 10 percent at 50 % AMI	2
At least an additional 15 percent at 50% AMI	4
At least an additional 20 percent at 50% AMI	6
20/50 Test serving 40 percent households	
At least an additional 5 percent at 40 % AMI	1
At least an additional 10 percent at 40 % AMI	2
At least an additional 15 percent at 40% AMI	4
At least an additional 20 percent at 40% AMI	6
At least 10% of units at 30% of AMI	6

3. **Development Characteristics.** **up to 23 points**

All selected amenities must be maintained, repaired, or replaced for the term of the LURC. For Development Characteristics also appearing in Serving Resident Populations with Special Housing Needs or Serving Resident Populations with Children, points may only be claimed once:

- a. Exterior materials: Choose 1

(i) Brick/stone veneer or stucco, minimum 60% and remaining exterior fiber cement and/or hardiplank: **4 points**

OR

(ii) Brick/stone veneer or stucco, minimum 50% and remaining exterior fiber cement and/or hardiplank: **3 points**

OR

(iii) Brick/stone veneer or stucco, minimum 40% and remaining exterior fiber cement and/or hardiplank: **2 points**

- b. Use of anti-fungal roofing materials with a minimum 30 year warranty: **2 points**
- c. Inclusion of a dog/pet park **1 point**
- d. Installation of hookups for standard size washers/dryers in all units: **3 points**
- e. Construct and/or rehabilitate a gazebo containing a minimum of 100 square feet; which must be covered and have permanent bench seating affixed and in an appropriate location available to all residents for year round usage: **2 points**
- f. Provide a keyed secure delivery area **2 points**
- g. Dedicated flex/case management office space **6 points**
- h. Provide a minimum 1,200 square foot community building accessible to residents during reasonable hours; including evenings, holidays and weekends. The square footage counted towards this total may include a leasing office, an equipped exercise room, and an equipped computer center. Laundry room and storage/maintenance rooms will not be counted as part of the 1,200 square foot minimum: **6 points**
- i. All units pre-wired, with hidden wiring, for high speed Internet hook-up with at least 1 centrally located connection port and connection ports in all bedrooms or if not wired, a wireless computer network: **5 points**

- j. Installation of a Range Oven, Fire Stop, Auto Stop or comparable extinguishing system over the stove in each unit: **6 points**
- k. Installation and maintenance of a camera video security system with at least one (1) camera monitoring each of the following areas: front of each building, back of each building, community room, computer center, rental office, all site entrance/exit roadways and parking areas: **2 points**
- l. Construction and maintenance of a walking trail, minimum four (4) feet wide and 1,250 linear feet paved and continuous. At least one (1) permanently anchored weather resistant bench with a back must be installed at the mid-point of the trail. Sidewalks are not eligible for these points. **2 points**
- m. Construction and maintenance of perimeter fencing extending around all sides of the development site, except at development entrances. Chain link fencing is not eligible for these points: **2 points**
- n. Construct and/or rehabilitate a pergola sized a minimum of 14 feet by 14 feet; that must have permanent bench seating affixed and in an appropriate location available to all residents for year round usage.: **2 points**
- o. Construct and/or rehabilitate a veranda that must be permanently attached to the side of a building. The veranda must be covered by a roof, be 10 feet wide and extend the length of the attached side of the building. The veranda must contain permanent seating for 10% of the units at the development and be available to all residents for year round usage:  
**2 points**
- p. Landscaped covered pavilion with permanent table, bench seating, and grills, in an appropriate location available to all residents for year-round usage, and on an accessible path:  
**2 points**
- q. The proposed development exclusively involves a structure or structures listed individually in the National Register of Historic Places, or is located in a registered historic district and certified by the Secretary of the U. S.

Department of the Interior as being of historical significance to the district. All proposed construction and/or rehabilitation shall be completed in such a manner as to be eligible for historic rehabilitation Housing Credit. Initial Applications seeking to combine historic nature and adaptive reuse will be treated as new construction. **2 points**

4. **Sponsor Characteristics: up to 7 points**

a. **Development Team Tennessee Housing Credit Experience up to 2 points**

To reward recent Housing Credit experience in Tennessee, developers associated with the Development Team listed in THOMAS for this Initial Application **MUST** have received an allocation of Housing Credit previously in Tennessee as evidenced by THDA’s issuance of IRS Form(s) 8609 for that development. The Applicant must identify the most recent Tennessee Housing Credit allocation received.

For developers partnering with an experienced Tennessee developer the Initial application must include the Developer and/or Joint Venture Agreements detailing these co-developing and fee arrangements with regard to the 2026 Initial Application. PHAs that are eligible shall receive two points.

Table 17–2: Development Team Prior Tennessee Allocations

Year of Most Recent Allocation	Points Available
2021–2025	2
2020 and before	1
No Tennessee Experience	0

b. **Development Team Track Record: up to 5 points**

To reward proven Tennessee Development Team experience, the Development Team will be awarded points as shown in Table 17–3 based on Minor SAEs. Minor SAE recording began on January 1, 2020. Minor SAEs are attributed by event to all individuals associated with the proposed Development Team; however, each event is counted only once regardless of the number of individuals tied to the same event. For example: Development Team A involves 20 individuals and Development Team B involves 3 individuals. Each team has a pre-2026 development with 2 Minor SAEs. For 2026, in Table 17-3, Development Team A would be assessed 2 cumulative Minor SAEs and receive 3 points. Development Team B also would be assessed 2 cumulative Minor SAEs and receive 3 points.

Table 17–3: Development Team Track Record

Cumulative Minor SAEs	Points Available
5+	0
4	1
2 to 3	3
0 to 1	5

5. **Water & Sewer:** **up to 4 points**

Points are available based on the status of availability of water and sewer to the proposed site:

Table 17–4: Water & Sewer

Status of Availability	Points Available
Public water & sewer approved and planned to site by the local jurisdiction OR on-site system financed and planned	2

Public water & sewer installed and available to the site OR  
on-site system financed and approved by the Tennessee Department of  
Environment & Conservation 4

6. **Financial Readiness to Proceed:** **up to 4 points**

Points are available based on the percentage of non-equity dollars committed to the project. Deferred developer fee is not counted as a non-equity source. Lenders and other funding sources will evidence their commitment to provide funding and disclose significant terms. Signed commitment letters, conditional commitment letters, loan agreements and grant agreements meet this requirement. However, proposal letters and letters of intent or interest do not meet this requirement:

Table 17–5: Financial Readiness to Proceed

Non-equity Dollars Committed	Points Available
0 - 25% of dollars committed	1
25.1 - 50% of dollars committed	2
50.1 - 75% of dollars committed	3
75.1 - 100% of dollars committed	4

7. **Design Development:** **up to 4 points**

Points are available depending upon the level of conceptual design work completed and included as a part of the Initial Application. The information provided by applicants to qualify for these points is not intended to require an exceptional capital outlay or complex architectural or engineering design work. The purpose is to broadly demonstrate to reviewing staff that buildings, infrastructure, and proposed amenities will fit on site, units will fit in buildings, etc., and that preliminary consideration

has been given to the appropriateness of the proposal to the site from a physical standpoint.

Table 17–6: Design Development

Conceptual Design Work Completed	Points Available
Schematic site plan only	1
Above + schematic floor plans	2
Above + schematic elevations	3
Above + construction drawings begun	4

**8. Planning & Zoning Process: up to 4 points**

Points will be awarded based on what stage the proposal is at in the planning & zoning process. Documentation shall be provided sufficient to demonstrate the planning & zoning stage.

Table 17–7: Planning & Zoning Process

Process Stage	Points Available
Has not begun	0
In process	2
By right or zoning approvals in place	4

**9. Public Housing Waiting List/Housing Choice Voucher Holder:**

**1 point**

Initial Applications electing these points must indicate priority for households currently on a Public Housing waiting list or who have been approved for a Housing Choice Voucher pending identification of a unit (“HCV Voucher Holder”). This priority must be clearly documented in marketing plans, lease-up plans, and operating policies and procedures

and provided with the Final Application.

10. **Serving Resident Populations with Special Housing Needs OR Serving Resident Populations with Children: 5 points**

Scattered Sites. Applicants for proposed scattered-site developments must submit a proposal for satisfying the amenity requirements outlined herein. Approval will be within THDA's sole discretion. The proposal must be submitted at least 60 days prior to the Initial Application deadline.

**10.1 Serving Resident Populations with Special Housing Needs.** Proposals intending to serve resident populations with special needs, must indicate this residency preference in the Initial Application, and, in addition, must include:

- a. Memorandum of agreement(s) or contract(s) with supportive service provider(s) to provide Supportive Services appropriate for the particular special needs population that meets the definition under Section 2 or, if the resident population is older persons, the definition of Supportive Services for Older Persons; and
- b. Contain dedicated space, with appropriate furniture and fixtures, relevant to the Special Housing Needs Resident Population for said supportive service providers and provide at least one (1) of the following on-site amenities under 10.1.d.; or
- c. If the proposed development is an incremental development or a subsequent phase development that will result in a total of more than 80 units of tax credit and non-tax credit units combined amongst all phases/increments, then the proposed phased/increment development must include two (2) additional on-site amenities than what was provided in the previous increment or phase. The two

amenities can be an additional dedicated space for supportive service providers and one amenity under 10.1.d. or two additional amenities under 5.d. than what was previously provided.

- d. Approved Onsite Amenities. All selected amenities must be maintained, repaired, or replaced for the term of the LURC.
  - (i) Construct and/or rehabilitate and maintain an exercise facility for appropriate group activity for special housing needs residents. The space must be at least 900 square feet, if indoor;
  - (ii) Construct and/or rehabilitate and maintain a gazebo containing a minimum of 100 square feet; which must be covered and have permanent bench seating affixed and in an appropriate location available to all residents for year round usage;
  - (iii) Construct and/or rehabilitate and maintain a pergola sized a minimum of 14 feet by 14 feet; which must have permanent bench seating affixed and in an appropriate location available to all residents for year round usage;
  - (iv) Construct and/or rehabilitate and maintain a veranda which must be permanently attached to the side of a building. The veranda must be covered by a roof, be 10 feet wide and extend the length of the attached side of the building. The veranda must contain permanent seating for 10 percent of the units at the development and be available to all residents for year round usage;
  - (v) Construct and/or rehabilitate and maintain a walking trail, minimum four (4) feet wide and 1250 linear feet paved and continuous. At least one (1) permanently anchored weather resistant bench with a back must be installed at the mid–point of the trail. Sidewalks are not eligible for these points;
  - (vi) Construct and/or rehabilitate and maintain a landscaped covered

pavilion with permanent table and bench seating and grills, in an appropriate location available to all residents for year-round usage, and on an accessible path;

- (vii) Construct and/or rehabilitate and maintain a fenced community garden with raised beds on an accessible path;
- (viii) Construct and/or rehabilitate and maintain furnished rooms for meeting or working that can be reserved by tenants free of charge, which are available for use outside normal business hours; or
- (ix) Provide in the proposed development's community room or computer center, updated computer systems equipped with high speed Internet service, which include new computers, new printers and new scanners purchased no earlier than 12 months prior to the placed in service date. The computers must be provided at a minimum of one (1) computer per 50 total units or part of 50 units. Printer cartridges, paper, computer supplies and on-going maintenance of the computer systems sufficient to meet reasonable resident demand must be furnished, free of charge, to residents. The computer system must be available to residents during regular office hours and occasionally during the evenings and weekends.

**10.2 Serving Resident Populations with Children.** Proposals serving resident populations with children must (i) indicate this residency preference in the Initial Application and (ii) must construct and/or rehabilitate the number of three (3) bedroom units that equals or exceeds a minimum of 20% of the total number of units in the development rounded up to the nearest whole unit. In addition, the proposal must include:

- a. An on-site playground with permanent playground equipment of commercial grade quality with a minimum of four separate pieces of

equipment or a structure that encompasses a minimum of four pieces of equipment AND at least one (1) of the following on-site amenities under 10..2.a.; or

- b. If the proposed development is an incremental development or a subsequent phase development that will result in a total of more than 80 units of tax credit and non-tax credit units combined amongst all phases, then the proposed phased development must include an additional two (2) on-site amenities under 10.2.a. or an additional onsite playground as described above and one (1) additional on-site amenities under 7.c. than what was provided under the previous increment or phase.
- c. Approved On-site Amenities. All selected amenities, including playgrounds, must be maintained, repaired, or replaced for the term of the LURC.
  - (i) Construct and/or rehabilitate and maintain an appropriately sized, dedicated space with appropriate furniture and fixtures for, and agreements with, providers of after-school tutoring/homework help programs. The space must be available to residents during regular office hours and occasionally during the evenings and weekends;
  - (ii) Construct and/or rehabilitate and maintain a sport field or court (basketball, tennis, baseball, field hockey, soccer, football, etc.) that incorporates permanent fixtures, a minimum of 1600 square feet, is surfaced appropriately for the sport(s) intended for that space, and is separate from all parking areas. The field or court must be available to all residents for year round use;
  - (iii) Provide in the proposed development's community room or computer center, updated computer systems equipped with high speed Internet service, which include new computers, new

printers and new scanners purchased no earlier than 12 months prior to the placed in service date. The computers must be provided at a minimum of one (1) computer per 50 total units or part of 50 units. Printer cartridges, paper, computer supplies and on-going maintenance of the computer systems sufficient to meet reasonable resident demand must be furnished, free of charge, to residents. The computer system must be available to residents during regular office hours and occasionally during the evenings and weekends;

- (iv) Construct and/or rehabilitate and maintain exercise/fitness center of at least 900 square feet that includes at least two pieces of commercial grade equipment, and, for properties with more than 50 units, one additional piece of commercial grade equipment per 25 units. Operating instructions must be posted for each piece of commercial grade equipment.
- (v) Construct and/or rehabilitate and maintain a walking trail, minimum four (4) feet wide and 1250 linear feet paved and continuous. At least one (1) permanently anchored weather resistant bench with a back must be installed at the mid-point of the trail. Sidewalks are not eligible for these points;
- (vi) Construct and/or rehabilitate and maintain a landscaped covered pavilion with permanent table and bench seating and grills, in an appropriate location available to all residents for year-round usage, and on an accessible path;
- (vii) Construct and/or rehabilitate and maintain a fenced community garden with raised beds on an accessible path; or
- (viii) Construct and/or rehabilitate and maintain furnished rooms for meeting or working that can be reserved by tenants free of charge, which are available for use outside normal business

hours.

**11. Development Intended for Eventual Resident Ownership: 1 point**

Applicants offering qualified residents the right of first refusal to purchase single family Housing Credit buildings at the end of the fifteen-year Compliance Period shall include, in the Initial Application, a detailed plan specifically including how the Owner will set aside a portion of the rent beginning in year two (2) of the Compliance Period to provide sufficient funds to the resident at the end of the Compliance Period for the down payment and closing costs to purchase the unit. The plan shall be required to be updated and re-submitted to THDA at the end of year thirteen (13) of the Compliance Period. The LURC will contain provisions ensuring enforcement of this provision. If these points are elected, an Initial Application is **not eligible for points in Section 16-A-14 and Section 16-A-15.**

**12. Energy Efficiency: up to 10 points**

- a. ENERGY STAR rated HVAC systems (15 SEER minimum or equivalent) in all units;  
(3 points)
- b. ENERGY STAR certified tankless water heater; (2 points)
- c. ENERGY STAR dishwasher; (2 points)
- d. ENERGY STAR refrigerator (19 cubic foot minimum) with ice maker;(2 points)
- e. ENERGY STAR rated windows in all units; (2 points)
- f. ENERGY STAR ceiling fans; (1 point)
- g. ENERGY STAR ventilation fans (range hood, bathroom). (1 point)

These ENERGY STAR requirements, if elected, must be met development wide when the development is placed in service.

**13. Tennessee Growth Policy Act: 5 points**

Initial Applications with proposed developments located completely and wholly in a county or municipality with an approved growth plan under the Tennessee Growth Policy Act.

**14. Waiver of the Qualified Contract Process: 9 points**

Initial Applications waiving the ability to participate in the QCP. If the Qualified Contract Process is waived, the Compliance Period within the LURC will be defined as thirty (30) years, unless there is an approved PILOT. If there is an approved PILOT, the Compliance Period will be defined as fifteen (15) years. The LURC will contain provisions ensuring enforcement of this provision. An Initial Application is **not eligible for these points if points are elected in Section 17–A–11.**

**15. Extended Recapitalization Waiver: up to 8 points**

Applicants may defer the point when recapitalization of the proposed development, through a subsequent allocation of Housing Credit under the competitive or noncompetitive process, may be requested. Points are based on the number of years from the date the last building in the development placed in service. An Initial Application is **not eligible for these points if points are elected in Section 17–A–11.**

Table 17 –8: Earliest Year When New Housing Credit May be Requested

Years From Date Last Building Placed in Service	Points Available
17	2
20	8

**B. Rehabilitation of Existing Multifamily Housing:**

The scoring criteria in this section are not intended to allow an Applicant to claim the maximum 100 points. An eligible Initial Application must provide a minimum score of **60 points** which will be confirmed during the scoring review process.

**1. Housing Credit Development Location: 2 points**

An Initial Application proposing a development and Housing Credit Development site wholly located within a HUD–defined QCT covered by a CCRP.

**2. Meeting Housing Needs: up to 13 points**

- a. An Initial Application will be eligible for points based on the number of years since the date of the most recent placed in service event for the last building placed in service in the proposed development. The most recent placed in service date for the last building placed in service will be confirmed by THDA, in its sole discretion. **up to 4 points**

Table 17–9: Time Since Last Placed in Service

Year Last Building Placed in Service	PHAs	Other
After 2008	0	0
2001 – 2008	1	1
1997 – 2000	2	2
1994 – 1996	3	4
Before 1994	4	3

- b. Initial Applications may receive these points (rounded down to the nearest 1/1,000<sup>th</sup> point) in proportion to the three (3) year average physical occupancy rate of the proposed development, rounded down to the nearest

1/1,000<sup>th</sup> percent. This three (3) year average physical occupancy rate shall be determined using both the occupied residential rental units which were charged rent as of December 1 during each of the previous three (3) years and the number of the total residential rental units determine at the last placed in service date for all the buildings in the development. Information must be certified by a CPA who shall confirm occupancy and rent information using December rent rolls for the prior three (3) years and the total number of residential rental units determined at the last placed in service date for all buildings in the development. For example, if the three (3) year average occupancy rate is 95.678%,  $0.95678 \times 3 = 2.870$  points. **up to 3 points**

- c. An Initial Application proposing “per door” rehabilitation hard costs in excess of the \$25,000 minimum will be eligible for points **up to 3 points**

Table 17–10: Proposed Rehabilitation Hard Costs per Unit

“Per Door” Rehabilitation Amount	Points Available
Less than \$26,000	0
\$26,001 to \$40,000	1
\$40,001 to \$50,000	2
\$50,001 and above	3

Initial Applications proposing to rehabilitate the highest percentage of the total of the currently existing affordable housing units in the county and the “pipeline” competitive and noncompetitive Housing Credit units in the county. Initial Applications may receive these points (rounded down to the nearest 1/1,000<sup>th</sup> point) in proportion to the ratio of post–rehabilitation Housing Credit units to the total of the currently existing affordable housing units in the county and the “pipeline” competitive and noncompetitive Housing Credit units in the county, rounded down to the nearest 1/1,000<sup>th</sup>

percent. The county– by–county total of the currently existing affordable housing units in the county, the “pipeline” competitive and noncompetitive Housing Credit units in the county, and existing USDA/RD units is available on the THOMAS Documents Page at:

<https://dogvxws799i6n.cloudfront.net/wp-content/uploads/2026-Unduplicated-Units-for-Existing-Scoring-2.pdf>.

(i) For example, if the number of post–rehabilitation Housing Credit units is 88, and the total of the currently existing affordable housing units in the county and the “pipeline” competitive and noncompetitive Housing Credit units in the county is 789,  $(88/789) \times 3 = 0.333$  points. **up to 3 points**

3. **Development Characteristics. up to 23 points**

All selected amenities must be maintained, repaired, or replaced for the term of the LURC. For Development Characteristics also appearing in Serving Resident Populations with Special Housing Needs or Serving Resident Populations with Children, points may only be claimed once:

a. Rehabilitating Existing Multifamily Housing in an area covered by a CCRP.  
5 points

b. Exterior materials: Choose 1

(i) Brick/stone veneer or stucco (minimum 60%) and remaining exterior fiber cement and/or hardiplank: **4 points**

OR

(ii) Brick/stone veneer or stucco (minimum 50%) and remaining exterior fiber cement and/or hardiplank: **3 points**

OR

(iii) Brick/stone veneer or stucco (minimum 40%) and remaining exterior fiber cement and/or hardiplank: **2 points**

c. Use of anti–fungal roofing materials with a minimum 30 year warranty: **2 points**

d. Install hookups for standard size washers/dryers in all units: **3 points**

e. Construct and/or rehabilitate a gazebo containing a minimum of 100 square feet; which must be covered and have permanent bench seating affixed and in an appropriate location available to all residents for year round usage:

**2 points**

- f. Provide a minimum 1,200 square foot community building accessible to residents during reasonable hours; including evenings, holidays and weekends. The square footage counted towards this total may include a leasing office, an equipped exercise room, and an equipped computer center. Laundry room and storage/maintenance rooms will not be counted as part of the 1,200 square foot minimum: **6 points**
- g. Pre-wire all units with hidden wiring, for high speed Internet hookup with at least 1 centrally located connection port or if not wired, then a wireless computer network: **2 points**
- h. Pre-wire all units with hidden wiring, for high speed Internet hook-up with at least 1 centrally located connection port and connection ports in all bedrooms or if not wired, a wireless computer network: **3 points**
- i. Install a Range Oven, Fire Stop, Auto Stop or comparable extinguishing system over the stove in each unit: **6 points**
- j. Install and maintain a camera video security system with at least one (1) camera monitoring each of the following areas: front of each building, back of each building, community room, computer center, rental office, all site entrance/exit roadways and parking areas: **2 points**
- k. Construct and maintain a walking trail, minimum four (4) feet wide and 1250 linear feet paved and continuous. At least one (1) permanently anchored weather resistant bench with a back must be installed at the mid-point of the trail. Sidewalks are not eligible for these points: **2 points**
- l. Construct and maintain perimeter fencing extending around all sides of the development site, except at development entrances. Chain link fencing is not eligible for these points: **2 points**
- m. Construct and/or rehabilitate a pergola sized a minimum of 14 feet by 14 feet with permanent bench seating affixed and in an appropriate location

available to all residents for year round usage: **2 points**

- n. Construct and/or rehabilitate a veranda which must be permanently attached to the side of a building. The veranda must be covered by a roof, be 10 feet wide and extend the length of the attached side of the building. The veranda must contain permanent seating for 10% of the units at the development and be available to all residents for year round usage: **2 points**

- o. Construct and/or rehabilitate a picnic shelter which must be covered, with permanent table and bench seating and in an appropriate location available to all residents for year round usage: **2 points**

- p. The proposed development exclusively involves a structure or structures listed individually in the National Register of Historic Places, or is located in a registered historic district and certified by the Secretary of the U. S. Department of the Interior as being of historical significance to the district. All proposed construction and/or rehabilitation shall be completed in such a manner as to be eligible for historic rehabilitation housing credit. Developments seeking to combine historic nature and adaptive reuse will be treated as new construction and are not eligible for the points in this Section 16-B-3-p. **5 points**

**4. Sponsor Characteristics: up to 10 points**

- a. Development Team Tennessee Housing Credit Experience **up to 5 points**  
To reward recent Housing Credit experience in Tennessee, developers associated with the Development Team listed in THOMAS for this Initial Application MUST have received an allocation of Housing Credit previously in Tennessee as evidenced by THDA's issuance of IRS Form(s) 8609 for that development. The Applicant must identify the most recent Tennessee Housing Credit allocation received.  
For developers partnering with an experienced Tennessee developer, the Initial Application must include the Developer and/or Joint Venture

agreements detailing these co-developing and fee arrangements with regard to the 2026 Initial Application. PHAs shall receive five points.

Table 17–11: Development Team Prior Tennessee Allocations

Year of Most Recent Allocation	Points Available
2021–2025	5
2020 and before	3
No Tennessee Experience	0

AND

- b. Development Team Track Record: **up to 5 points**

To reward proven Tennessee Development Team experience, the Development Team will be awarded points as shown in Table 17–12 based on Minor SAEs. Minor SAE recording began on January 1, 2019. Minor SAEs are attributed by event to all individuals associated with the proposed Development Team; however, each event is counted only once regardless of the number of individuals tied to the same event. For example: Development Team A involves 20 individuals and Development Team B involves 3 individuals. Each team has a pre-2026 development with 2 Minor SAEs. For 2026, in Table 17-12, Development Team A would be assessed 2 cumulative Minor SAEs and receive 3 points. Development Team B also would be assessed 2 cumulative Minor SAEs and receive 3 points.

Table 17-12: Development Team Track Record

Cumulative Minor SAEs	Points Available
5+	0

4	1
2 to 3	3
0 to 1	5

**5. Serving Resident Populations with Special Housing Needs: 7 points**

Points may be taken for Serving Resident Populations with Special Housing Needs or Serving Resident Populations with Children, but not both. Initial Applications electing these points must indicate a residency preference for households with Special Housing Needs.

The proposed development must include:

- a. Memorandum of agreement(s) or contract(s) with supportive service provider(s) to provide Supportive Services appropriate for the particular special needs population that meets the definition under Section 2 or, if the resident population is older persons, the definition of Supportive Services for Older Persons; and
- b. Contain dedicated space, with appropriate furniture and fixtures, relevant to the Special Housing Needs Resident Population for said supportive service providers and provide at least one (1) of the following on-site amenities under 5.d.; or
- c. If the proposed development is an incremental development or a subsequent phase development that will result in a total of more than 80 units of tax credit and non-tax credit units combined amongst all phases, then the proposed phased development must include two (2) additional on-site amenities than what was provided in the previous increment or phase. The two amenities can be an additional dedicated space for supportive service providers and one amenity under 5.d. or two additional amenities under 5.d. than what was previously provided.
- d. Approved Onsite Amenities. All selected amenities must be

maintained, repaired, or replaced for the term of the LURC.

- (i) Construct and/or rehabilitate and maintain an exercise facility for appropriate group activity for special housing needs residents. The space must be at least 900 square feet, if indoor;
- (ii) Construct and/or rehabilitate and maintain a gazebo containing a minimum of 100 square feet; which must be covered and have permanent bench seating affixed and in an appropriate location available to all residents for year round usage;
- (iii) Construct and/or rehabilitate and maintain a pergola sized a minimum of 14 feet by 14 feet; which must have permanent bench seating affixed and in an appropriate location available to all residents for year round usage;
- (iv) Construct and/or rehabilitate and maintain a veranda which must be permanently attached to the side of a building. The veranda must be covered by a roof, be 10 feet wide and extend the length of the attached side of the building. The veranda must contain permanent seating for 10 percent of the units at the development and be available to all residents for year round usage;
- (v) Construct and/or rehabilitate and maintain a walking trail, minimum four (4) feet wide and 1250 linear feet paved and continuous. At least one (1) permanently anchored weather resistant bench with a back must be installed at the mid–point of the trail. Sidewalks are not eligible for these points
- (vi) Construct and/or rehabilitate and maintain a landscaped covered pavilion with permanent table and bench seating and grills, in an appropriate location available to all residents for year-round usage, and on an accessible path;
- (vii) Construct and/or rehabilitate and maintain a fenced community

- garden with raised beds on an accessible path;
- (viii) Construct and/or rehabilitate and maintain furnished rooms for meeting or working that can be reserved by tenants free of charge, which are available for use outside normal business hours; or
  - (ix) Provide in the proposed development's community room or computer center, updated computer systems equipped with high speed Internet service, which include new computers, new printers and new scanners purchased no earlier than 12 months prior to the placed in service date. The computers must be provided at a minimum of one (1) computer per 50 total units or part of 50 units. Printer cartridges, paper, computer supplies and on-going maintenance of the computer systems sufficient to meet reasonable resident demand must be furnished, free of charge, to residents. The computer system must be available to residents during regular office hours and occasionally during the evenings and weekends.
- e. Scattered Sites. Applicants for proposed scattered-site developments must submit a proposal for satisfying the amenity requirement outlined herein. Approval will be within THDA's sole discretion. The proposal must be submitted at least 60 days prior to the Initial Application deadline.

**6. Public Housing Waiting List/Housing Choice Voucher Holder: 1 point**

Initial Applications electing these points must indicate priority for households currently on a Public Housing waiting list or who have been approved for a Housing Choice Voucher pending identification of a unit ("HCV Voucher Holder)". This priority must be clearly documented in marketing plans, lease-up plans, and operating policies and procedures and provided with the Final Application.

**7. Serving Resident Populations with Children:**

**7**

**points**

Points may be taken for Serving Resident Populations with Children or Serving Resident Populations with Special Housing Needs, but not both. Initial Applications electing these points must indicate a residency preference for households with children and must construct and/or rehabilitate the number of three (3) bedroom units that equals or exceeds a minimum of 20% of the total number of units in the development rounded up to the nearest whole unit.

The proposed development must include:

- a. An on-site playground with permanent playground equipment of commercial grade quality with a minimum of four separate pieces of equipment or a structure that encompasses a minimum of four pieces of equipment AND at least one (1) of the following on-site amenities under 7.c.; or
- b. If the proposed development is an incremental development or a subsequent phase development that will result in a total of more than 80 units of tax credit and non-tax credit units combined amongst all phases, then the proposed phased development must include an additional two (2) on-site amenities under 7.c. or an additional onsite playground as described above and one (1) additional on-site amenities under 7.c. than what was provided under the previous increment or phase.
- c. Approved On-site Amenities. All selected amenities, including playgrounds, must be maintained, repaired, or replaced for the term of the LURC.
  - i) Construct and/or rehabilitate and maintain an appropriately sized, dedicated space with appropriate furniture and fixtures for, and agreements with, providers of after-school tutoring or homework help programs. The space must be available to

residents during regular office hours and occasionally during the evenings and weekends;

- ii) Construct and/or rehabilitate and maintain a sport field or court (basketball, tennis, baseball, field hockey, soccer, football, etc.) that incorporates permanent fixtures, a minimum of 1600 square feet, is surfaced appropriately for the sport(s) intended for that space, and is separate from all parking areas. The field or court must be available to all residents for year round use;
- iii) Provide in the proposed development's community room or computer center, updated computer systems equipped with high speed Internet service, which include new computers, new printers and new scanners purchased no earlier than 12 months prior to the placed in service date. The computers must be provided at a minimum of one (1) computer per 50 total units or part of 50 units. Printer cartridges, paper, computer supplies and on-going maintenance of the computer systems sufficient to meet reasonable resident demand must be furnished, free of charge, to residents. The computer system must be available to residents during regular office hours and occasionally during the evenings and weekends;
- iv) Construct and/or rehabilitate and maintain an exercise room of at least 900 square feet with at least 3 pieces of new equipment; Exercise/fitness center of at least 900 square feet that includes at least two pieces of commercial grade equipment, and, for properties with more than 50 units, one additional piece of commercial grade equipment per 25 units. Operating instructions must be posted for each piece of commercial grade equipment;
- v) Construct and/or rehabilitate and maintain a walking trail,

minimum four (4) feet wide and 1250 linear feet paved and continuous. At least one (1) permanently anchored weather resistant bench with a back must be installed at the mid-point of the trail. Sidewalks are not eligible for these points; or

- vi) Construct and/or rehabilitate and maintain a landscaped covered pavilion with permanent table and bench seating and grills, in an appropriate location available to all residents for year-round usage, and on an accessible path; or
- vii) Construct and/or rehabilitate and maintain a fenced community garden with raised beds on an accessible path; or
- viii) Construct and/or rehabilitate and maintain furnished rooms for meeting or working that can be reserved by tenants free of charge, which are available for use outside normal business hours.

d. Scattered Sites. Applicants for proposed scattered-site developments must submit a proposal for satisfying the amenity requirement outlined herein. Approval will be within THDA's sole discretion. The proposal must be submitted at least 60 days prior to the Initial Application deadline.

**8. Development Intended for Eventual Resident Ownership: 4 points**

Applicants offering qualified residents the right of first refusal to purchase single family Housing Credit units at the end of the fifteen-year Compliance Period shall include, in the Initial Application, a detailed plan specifically including how the Owner will set aside a portion of the rent beginning in year two (2) of the Compliance Period to provide sufficient funds to the resident at the end of the Compliance Period for the down payment and closing costs to purchase the unit. The plan shall be updated and re-submitted to THDA at the end of year thirteen (13) of the Compliance Period. **If these points are elected, an Initial Application**

is not eligible for points in Section 17-B-11 and Section 17-B-12.

**9. Energy Efficiency: up to 10 points**

- a. ENERGY STAR rated HVAC systems (15 SEER minimum or equivalent) in all units; (3 points)
- b. ENERGY STAR certified tankless water heater; (2 points);
- c. ENERGY STAR refrigerator of 18 cubic foot minimum with ice maker (2 points);
- d. ENERGY STAR rated windows in all units; (2 points);
- e. ENERGY STAR ventilation fans (range hood, bathroom); (1 point).

**10. Tennessee Growth Policy Act: 5 points**

Initial Applications with proposed developments located completely and wholly in a county or municipality with a growth plan approved by the local government planning advisory committee as determined by the Tennessee Advisory Commission on Intergovernmental Relations

**11. Waiver of the Qualified Contract Process: 10 points**

Initial Applications waiving the ability to participate in the QCP. If the Qualified Contract Process is waived, the Compliance Period within the LURC will be defined as thirty (30) years, unless there is an approved PILOT. If there is an approved PILOT, the Compliance Period will be defined as fifteen (15) years. The LURC will contain provisions ensuring enforcement of this provision. **An Initial Application is not eligible for these points if points are elected in Section 17-A-11.**

**12. Extended Recapitalization Waiver: up to 8 points**

Applicants may defer the point when recapitalization of the proposed development, through a subsequent allocation of Housing Credit under the competitive or noncompetitive process, may be requested. Points are based on the number of years from the date the last building in the development placed in service. **An Initial Application is not eligible for**

**these points if points are taken in area Section 17–B–8 (Developments Intended for Eventual Resident Ownership).**

Table 17–13: Earliest Year When Recapitalization May be Requested

Number of Years Since Placed in Service	Points Available
17	2
20	8

**Section 18: Competitive Housing Tax Credit Calendar of Events**

The calendar of events applicable to this QAP is as shown below. These dates are subject to change at THDA’s sole discretion.

A full calendar will also be published on the THOMAS Documents Page.

Table 18–1: Calendar of Events

Dates	2026 Competitive Cycle
March 20, 2026	Competitive Cycle Opens for Initial Applications
April 16, 2026 (4:30 PM CT)	2026 Competitive Cycle Deadline for Initial Applications

## **Section 19: Initial Application Eligibility and Scoring Review**

### **A. Initial Application Review Process**

1. THDA will notify each Applicant when the eligibility determination and scoring of all Initial Applications is complete. THDA will send this notice to the contact person at the address specified in the Initial Application. Failure to receive any notice specified in this QAP will not extend deadlines or modify requirements. All Applicants shall immediately notify THDA at thomas@thda.org of changes in the name and/or address of the contact or alternate person specified in the Initial Application. Such notification by the Applicant will not be deemed to be an amendment to the Initial Application.
2. If THDA determines that an Initial Application meets all of the eligibility requirements of this QAP and if the score assigned by THDA in each scoring category is the same as or higher than the score assigned by the Applicant in the Initial Application, then no further action by the Applicant or THDA will be taken. Applicants shall not submit additional items for the purpose of increasing the score in a particular scoring category if the THDA assigned score for the Initial Application is the same as or higher than the score assigned by the Applicant in the Initial Application. The provisions of the Cure Period do not apply.
3. If THDA determines that an Initial Application does not meet one or more of the eligibility requirements of this QAP or if the score assigned by THDA in any scoring category is less than the score assigned by the Applicant in the Initial Application, THDA will provide a Cure Notice.
4. THDA will also provide a Cure Notice if THDA determines that (i) any two or more developments proposed in two or more Initial Applications constitute a single development for purposes of applying the development limit; or (ii) developers or Related Parties reflected in two or more Initial

Applications constitute a single entity for purposes of applying the developer or related party limitation.

5. THDA is not responsible for identifying all items for cure. If THDA finds an item that does not meet an eligibility requirement that was not identified for cure, then that item will be evaluated as is and issued a Review Notice and the Applicant may appeal.

#### **B. Cure Period**

1. Applicants receiving a Cure Notice may, in compliance with the requirements of this QAP, correct erroneous items, supply missing or incomplete items and/or may clarify any inconsistencies related to the specific items identified by THDA during the cure period which shall begin on the date of the Cure Notice and shall end at the time and date specified in the Cure Notice. The Cure Notice shall specify the means and methods identified issues may be remedied. Applicants may not submit additional items for the purpose of increasing the score in a particular scoring category where the THDA assigned score is the same as or higher than the score assigned by the Applicant in the Initial Application.
2. If additional documentation to address items specified in the Cure Notice is not submitted in accordance with the requirements contained in the Cure Notice, then the determination as to eligibility and scoring made by THDA is determinative. The review process described below is not available to Applicants who do not submit additional documentation, **in THOMAS**, in accordance with the Cure Notice (including, without limitation, the time deadlines specified therein.).
3. These cure provisions **do not apply** to Initial Applications that are not submitted in accordance with the Initial Application submission requirements of this QAP.
4. THDA will review all documentation submitted in accordance with the Cure Notice for each relevant Initial Application. If THDA determines

that an Initial Application, taking into account documentation submitted in accordance with the Cure Notice, meets all of the eligibility requirements of this QAP and if the score assigned by THDA in each scoring category is the same as or higher than the score assigned by the Applicant in the Initial Application, then no further action by the Applicant or THDA will be taken. The provisions of the Review Appeal Process will not apply.

5. If THDA determines that an Initial Application, taking into account documentation submitted in accordance with the Cure Notice, still does not meet all of the eligibility requirements of this QAP or if the score assigned by THDA in any scoring category is still less than the score assigned by the Applicant in the Initial Application, THDA will provide a Review Notice. The Review Notice will specify the time period within which a request for review may be made.

### **C. Review Appeal Process**

1. Applicants who receive a Review Notice may submit a request for review. This request for review must be submitted in THOMAS in accordance with the Review Notice and the THOMAS Documents Page. If no written request for review is submitted, no review will occur and the THDA determination prior to the issuance of the Review Notice will be final.
2. No additional documentation may be submitted in connection with this request for review. No information submitted after the expiration of the relevant cure period specified in the Cure Notice for an Initial Application will be considered. Requests for review that were not submitted in accordance with the Review Notice will not be considered.
3. The THDA Board of Directors, or a specially appointed body of its members, will meet in regular or special session in 2026 to evaluate the Initial Application, documentation submitted during the cure period, the Review Notice, the request for review and THDA staff analysis thereof (the "Review Meeting"). Applicants may not provide any further

documentation for the Review, regardless of whether the Applicant or a representative thereof is present at the Review Meeting.

4. The THDA Board of Directors or its specially appointed body will consider whether documentation submitted in the Initial Application or as a result of the Cure Notice, taking into account the analysis of THDA staff, is sufficient to meet the requirements of this QAP or is otherwise consistent with the spirit and intent of this QAP.
5. **Any contact with THDA Executive Director, any member of the THDA Board or its specially appointed body by any person or entity on behalf of any Initial Application between the date of the Review Notice and the date of the Review Meeting will be grounds for dismissal of the review request.**
6. Applicants or representatives may contact THDA Multifamily Programs staff regarding procedural matters only between the date of the Review Notice and the date of the Review Meeting, which contact will not constitute grounds for dismissal of a review request. Applicants or representatives may, but are not required to, appear at the Review Meeting. Notice of the decision of the THDA Board of Directors or its specially appointed body will be provided to the contact person specified in an Initial Applicant.
7. The final score for all Initial Applications will be determined after the Review Meeting. The THDA Board of Directors will not consider requests to review decisions. All decisions of the THDA Board of Directors or its specially appointed body are final. No matters with respect to eligibility or scoring under will be considered after the adjournment of the Review Meeting.

#### **D. Final Scoring**

After the completion of the cure period and completion of the review process, the final score for each Initial Application will be determined by THDA. The

Final Notice process is described in the THOMAS Documents Page.

**E. Application of Various Limits and Final Ranking Process**

Following the final scoring of each Initial Application, THDA will make reservations of Housing Credit to eligible Initial Applications based on final score, the amount of Housing Credit determined by THDA to be appropriate, and the application of all requirements, priorities, and limits contained in this QAP, including as specified below, in the following order:

1. **Non-Profit** Allocations – eligible Initial Applications as described in Section 12 of this QAP.
2. **Permanent Supportive Housing for the Homeless Set-Aside** – eligible Initial Applications as described in Section 13 of this QAP.
  - a. THDA will continue down the ranking of eligible Initial Applications in this set-aside until the last full reservation can be made. After the last full reservation is made, any remaining Housing Credit remaining will roll into New Construction.
3. **New Construction** General Priority Category – eligible Initial Applications as described in Section 14 of this QAP will be ranked in descending order within the regional housing needs area they fall under in Map 11-1.
  - a. THDA will award credits as follows until insufficient credits remain to award to the next highest scoring application:
    - (i) THDA will make awards to the highest scoring applications in each of the regional housing needs areas, capped at the number of projects in each region as outlined in Section 11.D.
4. **Existing Multifamily Housing** General Priority Category – eligible Initial Applications as described in Section 15 of this QAP.
5. **PHA** General Priority Category – eligible Initial Applications as described in Section 16 of this QAP.
6. In the event credits remain in the Total Credit Ceiling after awards have been

allocated as outlined above, THDA will make an allocation of credits to the next highest scoring Initial Application, regardless of location in the state, for which sufficient credits remain to make a full award.

7. Consistent with Section 11.B.1., THDA's obligation to allocate no less than 10% of the Total Credit Ceiling to Qualified Nonprofit Organizations is intended and expected to be met through the normal course of the competition established through this Qualified Allocation Plan. However, THDA reserves the right to prioritize and make allocations of Housing Credit to Qualified Nonprofit Organizations, regardless of category or ranking, as may be needed to meet the requirements of Section 42(h)(5).

#### **F. Tie Breaker**

1. In the event of a scoring tie between two or more Initial Applications proposing new construction at the cutoff for receipt of a Reservation Notice, the tie shall be broken by giving priority to the proposed new construction development in the Initial Application requesting the least amount of Housing Credit per Housing Credit unit.
  - a. If the tie is not broken by Section 18.F.1, priority will be given to the proposed new construction development located wholly within a QCT and covered by a CCRP.
2. In the event of a scoring tie between two or more Initial Applications proposing rehabilitation of Existing Multifamily Housing, the tie shall be broken by giving priority to the proposed development requesting the least amount of Housing Credit per Housing Credit unit.

#### **G. Preliminary Ranking List**

All Initial Applicants that have been earmarked for an annual allocation of Housing Credit in the applicable funding year will be listed on the Preliminary Ranking List that will be available at [www.thda.org](http://www.thda.org). This ranking is a preliminary confirmation of a reservation of Housing Credit.

#### **H. Reservation Letter Process**

1. THDA will provide a Reservation Notice.
2. The THOMAS Documents Page describes requirements that must be met, including timelines, for the reservation process.
3. In determining the initial amount of Housing Credit to be reflected in the Reservation Notice, THDA will use the costs, incomes, and expenses submitted in the Initial Application, as determined reasonable by THDA.
4. The final amount of Housing Credit allocated to each successful Applicant may be less than, but not be more than, the amount requested in the Initial Application, the amount specified in the Reservation Notice or the amount that will be reflected in the Carryover Allocation Agreement. Allocations

will be determined in connection with a Carryover Allocation Application and in connection with an evaluation at the time the development is placed in service, in accordance with Section 42(m)(2) and this QAP.

**I. Recapture of Housing Credit During Reservation Period**

1. THDA will cancel a Reservation Notice for failure to fully satisfy conditions imposed in connection with the Reservation Notice and for failure to provide satisfactory information or documentation required by the Reservation Notice by the deadlines specified in the Reservation Notice. When so cancelled, the Housing Credit referred to in the Reservation Notice is not available for the development specified in the Reservation Notice and will be made available to other qualified developments. Deadlines specified in the Reservation Notice are the dates upon which Housing Credit is deemed recaptured by THDA unless the conditions related to each deadline have been met on or before such deadline or unless an extension has been granted.
2. Housing Credit made available through a Reservation Notice may be voluntarily returned. Any such return means Housing Credit is not available for the development referenced in the Reservation Notice.
3. Any Housing Credit recaptured either by cancellation of a Reservation Notice or voluntarily returned will be reserved to the fullest extent practical to other qualified Initial Applications for Housing Credit as provided in this QAP.

## **Section 20: Carryover Allocation Process**

### **A. Qualifying for a Carryover Allocation**

An Applicant with a Reservation Notice for a development that will not place in service by December 31 of the year in which the Reservation Notice was issued may be eligible for a Carryover Allocation of Housing Credit (“Carryover Allocation”). In order to qualify for a Carryover Allocation, the ownership entity identified in the Initial Application must have ownership of the Site identified in the Initial Application and must have incurred costs of at least 10 percent of the reasonably expected basis in the development by the date specified in the Carryover Allocation Agreement.

### **B. THOMAS Carryover Allocation Application Submission Requirements**

1. To obtain a Carryover Allocation Agreement, a completed Carryover Allocation Application must be submitted in THOMAS by the date specified by THDA. The Carryover Allocation Application must include, without limitation, the following:
  - a. An executed Statement of Application and Certification in the form shown on the Template and provided in THOMAS accordance with the Guidelines on the THOMAS Documents Page.
  - b. A copy of firm commitment letter(s) for construction financing, executed by all parties and otherwise in a form and with substance acceptable to THDA in its sole discretion. construction
  - c. A copy of the syndication transaction including, without limitation a firm commitment letter from the purchaser of the housing credits executed as specified in the Carryover Allocation Agreement.
  - d. A copy of the recent utility allowance documentation indicating the basis for calculations of utility costs for the size and type of units proposed as indicated in the Initial Application
  - e. A 30-year pro-forma for the proposed development in the Carryover

Application

- f. A copy of the IRS documentation reflecting Employer Identification Number for Owner.
  - g. A copy of the Owner's Affirmatively Furthering Fair Housing Marketing Plan. See Section 10.A.1. for requirements.
  - h. An executed copy of the most recent partnership agreement or operating agreement and current organizational chart for the Ownership Entity.
- 2. The Owner must execute a Carryover Allocation Agreement and return the executed Carryover Allocation Agreement to THDA no later than the date specified in the Carryover Allocation Agreement.
  - 3. If closing has occurred, the Owner must submit (through THOMAS) equity syndication closing documentation and construction financing closing documentation.
  - 4. The Owner must submit the Cost Certification for the 10 Percent Test in THOMAS no later than the date specified in the Carryover Allocation Agreement.
    - a. If available, a recorded warranty deed showing ownership by the ownership entity identified in the Initial Application, or a fully executed 50-year ground lease (subject to the provisions of this QAP) showing the ownership entity identified in the Initial Application as the lessee, a copy of recorded warranty deed or ground lease, as applicable, must be submitted.
    - b. If a PILOT agreement is available, a copy of the PILOT agreement must be submitted.

**C. Carryover Allocation Application Review Process**

During the review of the Carryover Allocation Application, THDA will issue Evaluation Notices to request additional documentation and/or information

for purposes of clarifying eligibility, scoring and financial feasibility. Evaluation Notices will be issued in the following manner:

Table 20–1: Schedule of Evaluation Notices and Deadlines

Evaluation Notice	Deadline for Response
First	5 business days from the date of the Evaluation Notice
Second	2 business days from the date of the Evaluation Notice
Final	1 business day from the date of the Evaluation Notice

THDA will not issue a Carryover Allocation Agreement if the conditions contained in Evaluation Notices issued in connection with the Carryover Allocation Application are not fully satisfied. Deadlines specified in the Final Evaluation Notice are the dates upon which Housing Credit may be recaptured by THDA if the conditions related to the deadline have not been met. Upon notification, the Housing Credit referred to in the Reservation Notice is not available for the development and will be made available to other qualified developments.

**D. Housing Credit Available**

The amount of Housing Credit reflected in a Carryover Allocation Agreement will be determined by THDA in connection with an evaluation at the time a Carryover Allocation is requested. The amount of Housing Credit may be less than, but will not be more than, the Housing Credit amount in the Reservation Notice.

**E. Status Reports**

Following execution of a Carryover Allocation Agreement, THDA may request status reports outlining progress towards completion by dates, in a form and with substance all as specified by THDA in its sole discretion.

**F. Recapture of Housing Credit During Carryover Period**

1. THDA will cancel a Carryover Allocation Agreement if there is a failure to fully satisfy conditions imposed in connection with the Carryover Allocation Agreement by the deadlines specified by THDA. When so cancelled, the Housing Credit referred to in the Carryover Allocation Agreement is not available for the development specified in the Carryover Allocation Agreement and will be made available to other qualified developments. Deadlines specified in the Carryover Allocation Agreement are the dates upon which Housing Credit is deemed recaptured by THDA if the conditions related to each deadline have not been met on or before such deadlines or unless an extension has been granted.
2. Housing Credit allocated through a Carryover Allocation Agreement may be voluntarily returned by the Owner. Upon return, the Housing Credit referred to in the Carryover Allocation Agreement is not available for the development specified in the Carryover Allocation Agreement.
3. Any Housing Credit recaptured either by cancellation of a Carryover Allocation Agreement or by voluntary return by the Owner will be made available as follows:
  - a. Any Housing Credit returned before October 1, 2026 will be reserved to other qualified 2026 Initial Applications for Housing Credit as provided in this QAP.
  - b. Any Housing Credit returned on or after October 1, 2026 will be available in 2027.

## **Section 21: Housing Credit Exchanges**

Notwithstanding any other provisions of this QAP, relief for certain developments is available as follows:

A. 2024 Competitive Housing Credit allocation recipients, subject to each of the following:

1. The maximum **aggregate** Housing Credit allocated to housing credit exchange allocations is limited to the amount of 2024 Housing Credit returned.
2. Developments which have received a previous housing credit exchange allocation **will not be eligible for a subsequent additional housing credit exchange allocation.**
3. Each Housing Credit Exchange Allocation shall be subject to the following additional conditions:
  - a. Developments intending to seek approval for a housing credit exchange allocation must so **notify THDA in writing no later than December 3, 2025.** Notification must be sent **via email** to [TNAallocation@thda.org](mailto:TNAallocation@thda.org).
  - b. Scoring selections and threshold requirements from the 2024 QAP, as applicable, will be enforced, otherwise the 2026 QAP will apply.
  - c. The ability to request the Qualified Contract Process for the particular development is permanently waived.
  - d. The Placed-In-Service deadline for housing credit exchange allocations will be December 31, 2028. Failure to meet or the request of an extension to the applicable deadline **will be** a Major Significant Adverse Event under Section 5-A of this QAP.
  - g. Housing credit exchange allocation developments will not be permitted to increase developer or consultant fees.
4. Other provisions applicable to housing credit exchange allocations:
  - a. Returned Housing Credit will not increase 2025 set-asides or pools.

- b. Housing credit exchange allocations will not count against county, developer, or other limits in the 2026 QAP.

**Section 22: Developments Financed with Tax-Exempt Bonds**

**A. Allocation Requirements**

Developments financed with tax-exempt bonds issued as a result of an award of MTBA may be eligible for allocations of Noncompetitive Housing Credit outside of the competitive process described in this QAP. The annual Noncompetitive Housing Credit will be determined by THDA in connection with the Initial Application evaluation of financial feasibility. These developments must meet the following conditions:

1. Applicants applying for Noncompetitive Housing Credit and MTBA must demonstrate that a minimum of 50%, or such other threshold as may be established by subsequent legislation, of the outstanding principal amount of tax-exempt bonds originally issued using an award of MTBA remain outstanding as of the placed in service date for the development. On that date, the outstanding principal amount of tax-exempt bonds originally issued using an award of MTBA must meet the requirements of Section 42(h)(4). Either bond counsel or a certified public accountant licensed in Tennessee must certify to THDA that this financing requirement is met.
2. Applicants applying for MTBA in THOMAS are deemed to be simultaneously applying for Noncompetitive Housing Credit in THOMAS. THDA will determine the amount of Noncompetitive Housing Credit to be allocated and will issue a Firm 42(m) Letter or a Conditional 42(m) Letter. In determining the initial amount of Noncompetitive Housing Credit to be reserved, THDA will use the costs, incomes and expenses submitted in the Initial Application as determined to be reasonable by THDA. Allocations are subject to Section 42(m)(2) and this QAP. Any allocation of Noncompetitive Housing Credit will not count against the

limits on Housing Credit by county, developer and related parties as specified in this QAP.

3. Applicants applying for MTBA and Noncompetitive Housing Credit are subject to the requirements in the 2026 MTBA Program Description.
4. If an Initial Application for Competitive Housing Credit and an application for MTBA and Noncompetitive Housing Credit for the same development is submitted, outside of the Economic Development Area Set-Aside, the Initial Application for Competitive Housing Credit will be deemed ineligible for further consideration, see Section 12 of the 2026 MTBA Program Description.
5. Applicants must agree to not participate in the Qualified Contract process.

**B. Development Limits**

The maximum amount of MTBA that may be allocated to a single development is described in Section 5 of the Multifamily Tax-Exempt Bond Authority Program Description for 2026. An applicant may submit a written request for an exception to the maximum MTBA amount listed in Section 5-A of the MTBA PD. The written request must include sufficient supporting documentation and information to substantiate the need for additional MTBA as determined by THDA, in its sole discretion. Only one (1) written request for an exception to the maximum MTBA limit per application will be considered. Written requests for exceptions to the maximum MTBA may be granted or denied by THDA, in its sole discretion

**C. Total Development Cost Limits**

Total Development Cost limits as specified in Table 22–1 below will be applied to all proposed developments requesting Noncompetitive Housing Credits at the time of Initial Application. The cost of issuance and any deferred portion of the developer fee over 15% will be excluded from these costs. An Applicant may submit a written request for an exception to the Total Development Cost limits. The written request must include sufficient supporting documentation

and information to substantiate the need for the exception, as determined by THDA, in its sole discretion. Only one

(1) written request for an exception to the Total Development Cost limits per application may be submitted.

**D. Limit on Contractor Fees, Profit, Overhead and General Requirements**

1. The total contractor fees, including contractor profit, contractor overhead and general requirements, shall not exceed 14% of total site work costs plus cost of accessory buildings plus either new building hard costs or rehabilitation hard costs, as determined by THDA, broken down as follows:

Table 22–1: Contractor Fees, Profit, Overhead and General Requirements

Limitations

Fee Description	Fee Amount
Contractor Profit	<=6 percent
Contractor Overhead	<=2 percent
Contractor General Requirements (incl payment and perf)	<=6 percent
Total Contractor Fees	<=14 percent

**E. Total Development Cost Limits**

In order to be eligible, Initial Applications for Housing Credit must propose Total Development Costs that do not exceed the applicable amount in Table 22–2 below. The Total Development Cost Limits are applied at Initial Application. Land cost is not included in the Total Development Cost for purposes of this calculation.

**Table 22–2: Total Development Cost Limits Per Unit by Development Type**

<b>Development Type</b>	<b>1 BR</b>	<b>2 BR</b>	<b>3 BR</b>	<b>4 BR</b>	<b>5 BR</b>
<b>Urban</b>					
Detached/ Semi-detached	\$294,000	\$351,600	\$418,800	\$493,200	\$540,000
Row House	\$261,600	\$316,800	\$387,600	\$460,800	\$506,400
Walkup	\$237,600	\$301,200	\$396,000	\$489,600	\$552,000
Elevator	\$248,400	\$319,200	\$426,000	\$531,600	\$602,400
<b>Suburban</b>					
Detached/ Semi-detached	\$280,800	\$335,880	\$399,600	\$470,400	\$514,800
Row House	\$249,600	\$302,400	\$369,600	\$439,200	\$483,600
Walkup	\$189,000	\$239,000	\$314,000	\$389,000	\$438,000
Elevator	\$197,000	\$254,000	\$405,600	\$507,600	\$574,800
<b>Rural</b>					
Detached/ Semi-detached	\$267,600	\$320,400	\$381,600	\$448,800	\$490,800
Row House	\$237,600	\$289,200	\$352,800	\$418,800	\$460,800
Walkup	\$216,000	\$273,600	\$360,000	\$445,200	\$501,600

Elevator                    \$225,600   \$290,400   \$387,600   \$483,600   \$548,400

**F. Capitalized Terms**

All capitalized terms used in this Section 22 shall have the meaning ascribed to them in this Section 22 or in Section 2 of this QAP or in the MTBA Program Description for 2026.

**PART IV: ADOPTION AND APPROVAL BY THE GOVERNOR**

**Section 23: Adoption and Approval by the Governor**

As provided in Executive Order No. 73, dated October 31, 2018 (the "Executive Order"), I, Bill Lee, the Governor of the State of Tennessee, do hereby designate the Tennessee Housing Development Agency (THDA) to be the housing credit agency for this State and, by my execution of this Qualified Allocation Plan, I hereby adopt this Qualified Allocation Plan as my plan for the distribution and administration of Housing Credits in the State of Tennessee, in conformance with Section 42 of the Internal Revenue Code of 1986, as amended and the Executive Order. As also provided in the Executive Order, this Qualified Allocation Plan shall be incorporated, by this reference, into and encompassed by the Executive Order as if set forth in the Executive Order verbatim.

---

**Bill Lee, Governor**

---

**Date**

**PART IV: ADOPTION AND APPROVAL BY THE GOVERNOR**

**Section 23: Adoption and Approval by the Governor**

As provided in Executive Order No. 73, dated October 31, 2018 (the "Executive Order"), I, Bill Lee, the Governor of the State of Tennessee, do hereby designate the Tennessee Housing Development Agency (THDA) to be the housing credit agency for this State and, by my execution of this Qualified Allocation Plan, I hereby adopt this Qualified Allocation Plan as my plan for the distribution and administration of Housing Credits in the State of Tennessee, in conformance with Section 42 of the Internal Revenue Code of 1986, as amended and the Executive Order. As also provided in the Executive Order, this Qualified Allocation Plan shall be incorporated, by this reference, into and encompassed by the Executive Order as if set forth in the Executive Order verbatim.

  
\_\_\_\_\_  
Bill Lee, Governor

  
\_\_\_\_\_  
Date